

ARCHITECTURE AND SITE REVIEW

SURREY FARMS - LOT 3 (S-24-025)

A RESIDENTIAL DEVELOPMENT



SI PROJECT TS418510 PLU PERMIT#148510TS.LOT3.DWG

TABLE OF CONTENTS

PLANNING/CIVIL ENGINEERING	ARCHITECTURE	LANDSCAPE
1.0 TITLE SHEET	G0 TITLE PAGE/PROJECT INFO	T-1 TREE MITIGATION AND PROTECTION PLAN
2.0 EXISTING CONDITIONS	G1.0 EXISTING SITE PHOTOS	T-2 TREE EVALUATION TABLE
2.1 OVERALL SITE PLAN	A1.1 SITE PLAN & GROUND FLOOR PLAN	T.3 TREE APPRAISAL TABLE
2.2 SITE PLAN	A1.2 FLOOR PLANS	T-4 TREE PROTECTION FENCING DETAIL
3.0 PRELIMINARY GRADING & DRAINAGE PLAN	A2.1 ELEVATIONS/ COLOR & MATERIALS	AND NOTES
3.1 PRELIMINARY GRADING SECTIONS	A2.2 ELEVATIONS/COLOR & MATERIALS	10.0 LANDSCAPE PLAN
4.0 UTILITY PLAN	A3.0 BUILDING SECTIONS	10.1 PLANTING LEGEND AND NOTES
5.0 STORMWATER CONTROL PLAN	A3.1 STREET ELEVATIONS/SITE SECTIONS	10.2 LANDSCAPE DETAILS
5.1 STORMWATER CONTROL	A4.1 SHADOW ANALYSIS	10.3 HYDROZONE PLAN
HYDROMODIFICATION AND DETAILS		10.4 IRRIGATION DETAILS
6.0 EROSION CONTROL PLAN		10.5 CONCEPT IMAGERY
6.1 EROSION CONTROL PLAN		P1 CONCEPTUAL LIGHTING PLAN
6.2 EROSION CONTROL DETAILS		
6.3 EROSION CONTROL DETAILS		
6.4 BASMAA		
7.0 FIRE ACCESS PLAN		
7.1 FIRE ACCESS PLAN		
7.2 FIRE TRUCK TURNAROUND		

PROJECT DATA

Lot 3 (S24-025) - APN 532-16-006, 178 Twin Oaks Drive			
	Existing	Proposed	Required
General Plan Designation	Agriculture	Agriculture	Agriculture
Zoning	RC	RC	RC
Use	Williamson Act	Single Family Residence	
Housing Unit Affordability	N/A	Market	
Gross Lot Size	N/A	23931 sf	20 acre minimum
Average Slope	15.2%	13.23%	
Reduction Factor	N/A	20.43%	
Net Lot Size	N/A	19042	
Lot Frontage	N/A	131.93	N/A
Lot Depth	N/A	171.9'	N/A
Height	N/A	38'	25 ft max per HDS&G /18' vis
Gross Floor Area			
Countable Attic	N/A	780	
Second Floor	N/A	2807	
First Floor	N/A	2987	
Accessory Buildings	N/A	N/A	
		6827 (includes 253 sf of garage)	
Total Countable SF	N/A	4700 sf	
Garage	N/A	653	up to 400 sf excluded from total
Below Grade SF (exempt)	N/A	N/A	Exempt
			800 sf of extra floor area allowed. Max unit size is 1,200 sf
ADU	N/A	N/A	
Lot Coverage	N/A	21.6%	N/A in RC
Setbacks			
Front	N/A	39.36'	30'
Side	N/A	8.48'	20'
Side	N/A	54.8'	20'
Rear	N/A	44.1'	25'
Parking	N/A	2 spaces garage, 2 on-site	2 spaces, 4 on-site guest parking

*Reduction Factor based on existing average slope

PROJECT DESCRIPTION

ARCHITECTURE & SITE REVIEW FOR A SINGLE FAMILY HOUSE ON THE 0.55-ACRE PROPOSED LOT 3 (S-24-025) OF SUBDIVISION APPLICATION M-24-013.

DEVELOPMENT TEAM

GOVERNMENT AGENCIES:

TOWN OF LOS GATOS
CONTACT: ERIN WALTERS

PLANNER/CIVIL ENGINEER:

HMH ENGINEERS
CONTACT: DEENA MORSILLI
1570 OAKLAND ROAD
SAN JOSE, CA 95131
(669)221-7817

OWNER:

LARRY DODGE
CONTACT: JIM FOLEY
223 W MAIN STREET
LOS GATOS, CA 95030
(408) 813-7490

ARCHITECT:

PLATFORM ARCHITECTURE & PLANNING
CONTACT: CHRIS HALL
1804 5TH STREET
BERKELEY, CA 94710
(415)658-1723

LANDSCAPE ARCHITECT:

HMH LANDSCAPE ARCHITECTURE
CONTACT: SHAWN TAYLOR
1570 OAKLAND ROAD
SAN JOSE, CA 95131
(408)487-2200

SURREY FARM ESTATES
LOT 3 (S-24-025)
178 TWIN OAKS DRIVE
ARCHITECTURE & SITE REVIEW

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION

TITLE SHEET

1.0

LEGEND

EXISTING



PROJECT BOUNDARY	
LOT LINE	
EASEMENT	
CURB AND GUTTER	
STORM DRAIN PIPE	
SANITARY SEWER PIPE	
OVERHEAD ELECTRICAL LINE	
WATER PIPE	
FENCE	
DRAINAGE ARROW	
TREE AND DRIPLINE	
ELECTROLIER	
COMMUNICATIONS MANHOLE	
STORM DRAIN MANHOLE	
SANITARY SEWER MANHOLE	
FIRE HYDRANT	
PULL BOX/METER/VULT	
SIGN	
RIPARIAN AREA	

ABBREVIATIONS

CL	CENTER LINE
EG	EXISTING GROUND
ESMT	EASEMENT
EX(E)	EXISTING
PSE	PUBLIC SERVICE EASEMENT
PUE	PUBLIC UTILITY EASEMENT
R/W	RIGHT OF WAY
SCVWD	SANTA CLARA VALLEY WATER DISTRICT
SD	STORM DRAIN
SDE	STORM DRAIN EASEMENT
SS	SANITARY SEWER
SSE	SANITARY SEWER EASEMENT
TYP	TYPICAL
W	WATER

EXISTING CONDITIONS NOTES:

1. SEE SHEET 2.2 FOR EXISTING TREE DATA TABLE



SURREY FARM ESTATES

LOT 3 (S-24-025)

178 TWIN OAKS DRIVE

ARCHITECTURE & SITE REVIEW

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
DATE	DESCRIPTION
OBJECT NO:	4185.10
3D DWG FILE:	418510EX_L0T3.DWG
SIGNED BY:	RH
DRAWN BY:	NW
CHECKED BY:	RH
DATE:	MAY 31ST, 2024
FAILE:	1" = 20'
HMH	

EXISTING CONDITIONS


2-0



SURREY FARM ESTATES
LOT 3 (S-24-025)
178 TWIN OAKS DRIVE
ARCHITECTURE & SITE REVIEW

10/17/2025	PER CITY COMMENTS	
9/15/2025	PER CITY COMMENTS	
7/25/2025	PER CITY COMMENTS	
4/18/2025	PER CITY COMMENTS	
3/31/2025	PER CITY COMMENTS	
NO	DATE	DESCRIPTION
PROJECT NO:		4185...
CAD DWG FILE:		418510SP OVERALL_LOT 3.DWG
DESIGNED BY:		C
DRAWN BY:		N
CHECKED BY:		C
DATE:	MAY 31ST, 2025	
SCALE:	1" = 5'	
(C) HMH		

OVERALL SITE PLAN



LEGEND

PROJECT BOUNDARY	—
LOT LINE (EXISTING)	—
LOT LINE (PROPOSED)	—
EASEMENT (EXISTING)	- - -
EASEMENT (PROPOSED)	- - -
YARD (REQUIRED)	—
RIPARIAN AREA	—
BIORETENTION AREA	—
WETLAND AREA	—
AREA OVER 30% SLOPE	—

0 5 10 20
1 INCH = 10 FEET

ABBREVIATIONS

(E)	EXISTING
(P)	PROPOSED
ESMT	EASEMENT
SSE	SANITARY SEWER EASEMENT (PUBLIC)
SDE	STORM DRAIN EASEMENT (PUBLIC)
EAE	EMERGENCY ACCESS EASEMENT
FSDE	PRIVATE STORM DRAIN EASEMENT
FSE	PUBLIC SERVICE EASEMENT

NOTES

- COVENANTS SHALL BE REQUIRED FOR MAINTENANCE OF THE PRIVATE ROAD BINDING EACH LOT OWNER AND ALL SUBSEQUENT LOT OWNERS, SUCH THAT BY ACCEPTANCE OF A DEED OR OTHER CONVEYANCE, IS DEEMED TO COVENANT AND AGREE THAT IF AT ANY TIME THE TOWN OF LOS GATOS CONCLUDES THAT MAINTENANCE OF THE ROADWAY INCLUDED IN THE COMMON PROPERTY IS NECESSARY AND HAS NOT BEEN DONE BY THE ASSOCIATION, THE TOWN OF LOS GATOS MAY PERFORM SUCH MAINTENANCE AS AGENT FOR THE ASSOCIATION, AND THE TOWN OF LOS GATOS WILL CHARGE THE ASSOCIATION FOR THE COST OF ANY SUCH MAINTENANCE, WHICH CHARGE SHALL BE AN OBLIGATION OF THE ASSOCIATION. SUCH REIMBURSEMENT SHALL BE A COST SUBJECT TO ASSESSMENT, AND THERE SHALL BE A LIEN ON THE PROPERTY, WHICH MAY BE PLACED ON THE TAX BILL AND COLLECTED AS ORDINARY TAXES BY THE TOWN.


LOT AREA	23931 SF / 0.55 ACRES
EXISTING CONTOUR LENGTHS	3634.42'
CONTOUR INTERVALS	1'
EXISTING AVERAGE SLOPE	15.22%
PROPOSED CONTOUR LENGTHS	3159.13'
CONTOUR INTERVALS	1'
PROPOSED AVERAGE SLOPE	13.23%


TREE #	Botanical Name	Common Name	DBH (Inches)	Height (FT)	Canopy Size (FT)	Protected Tree	Large Protected Tree	Health Rating	Preservation Suitability	Remove?	Notes
535	Quercus agrifolia	Coast Live Oak	8.0	28	15	X	4	HIGH	SAVE		
536	Olea europaea	Olive	5.0	31	18	X	4	HIGH	REMOVE		
537	Olea europaea	Olive	4.0	16	18	X	4	MODERATE	REMOVE		
538	Olea europaea	Olive	4.0	36	20	X	4	HIGH	REMOVE		
539	Quercus agrifolia	Coast Live Oak	4.0	15	10	X	3	HIGH	SAVE		
540	Quercus lobata	Valley Oak	13.0	35	28	X	3	MODERATE	REMOVE	Poor Tree Structure	
541	Quercus lobata	Valley Oak	17.0	50	33	X	3	MODERATE	REMOVE	Dead Wood	
543	Quercus lobata	Valley Oak	4.0	24	1	X	2	LOW	REMOVE	Severe Decline	
544	Quercus agrifolia	Coast Live Oak	7.0	32	8	X	4	HIGH	REMOVE		
545	Quercus lobata	Valley Oak	13.0	34	2	X	2	LOW	REMOVE	Severe Decline	
546	Quercus agrifolia	Coast Live Oak	8.0	28	12	X	4	HIGH	REMOVE		
547	Quercus agrifolia	Coast Live Oak	15.0	42	23	X	4	HIGH	REMOVE		
548	Quercus lobata	Valley Oak	11.0	38	12	X	2	LOW	REMOVE	Severe Decline	
549	Quercus lobata	Valley Oak	15.0	36	20	X	2	MODERATE	REMOVE	Dead Wood	
550	Quercus agrifolia	Coast Live Oak	9.0	22	20	X	4	HIGH	REMOVE	Crowded Growing Conditions	
551	Quercus lobata	Valley Oak	17.0	40	34	X	3	MODERATE	REMOVE	Severe Decline	
552	Olea europaea	Olive	4.0	17	23	X	4	MODERATE	REMOVE		
553	Quercus agrifolia	Coast Live Oak	12.0	28	16	X	4	HIGH	REMOVE		
554	Quercus agrifolia	Coast Live Oak	8.0	25	13	X	4	HIGH	REMOVE		
555	Quercus agrifolia	Coast Live Oak	9.0	31	20	X	4	HIGH	REMOVE		
556	Quercus lobata	Valley Oak	15.0	42	25	X	3	MODERATE	REMOVE	Dead Limbs	
557	Quercus lobata	Valley Oak	18.0	30	31	X	4	MODERATE	REMOVE	Dead Limbs	
558	Quercus lobata	Valley Oak	13.0	27	24	X	4	MODERATE	REMOVE	Dead Limbs	
559	Quercus lobata	Valley Oak	9.0	34	12	X	3	MODERATE	REMOVE	Severe Decline	
560	Quercus lobata	Valley Oak	16.0	41	27	X	4	MODERATE	REMOVE		
561	Olea europaea	Olive	8.0	26	23	X	2	LOW	REMOVE	Severe Decline	
562	Quercus lobata	Valley Oak	26.0	48	40	X	4	HIGH	REMOVE	Dead Wood	
563	Quercus agrifolia	Coast Live Oak	9.0	30	28	X	4	HIGH	REMOVE		
564	Quercus lobata	Valley Oak	28.0	44	46	X	3	MODERATE	REMOVE		
565	Quercus lobata	Valley Oak	17.0	42	23	X	4	MODERATE	REMOVE	Dead Limbs	
566	Quercus agrifolia	Coast Live Oak	36.0	42	38	X	5	HIGH	SAVE		
567	Quercus lobata	Valley Oak	19.0	40	33	X	4	MODERATE	REMOVE	Dead Wood	
568	Quercus lobata	Valley Oak	22.0	46	30	X	3	MODERATE	REMOVE	Dead Wood	
569	Quercus lobata	Valley Oak	35.0	42	30	X	4	MODERATE	SAVE		
570	Pyrus calleryana	Ornamental Pear	7.0	23	13	X	2	LOW	REMOVE	Severe Decline	
593	Quercus agrifolia	Coast Live Oak	9.0	26	20	X	4	HIGH	REMOVE		
594	Quercus agrifolia	Coast Live Oak	16.0	28	26	X	5	HIGH	REMOVE		
595	Quercus agrifolia	Coast Live Oak	12.0	27	21	X	5	HIGH	REMOVE		
596	Quercus agrifolia	Coast Live Oak	15.0	27	24	X	5	HIGH	REMOVE		
600	Quercus agrifolia	Coast Live Oak	22.0	42	35	X	4	HIGH	REMOVE	Dead Limbs	
601	Quercus agrifolia	Coast Live Oak	27.0	30	28	X	5	HIGH	REMOVE		



SURREY FARM ESTATES
LOT 3 (S-24-025)
178 TWIN OAKS DRIVE
ARCHITECTURE & SITE REVIEW

SITE PLAN





ABBREVIATIONS


CI	CURB INLET
ESMT	EASEMENT
EX(E)	EXISTING
FH	FIRE HYDRANT
INV	INVERT
IRR	IRRIGATION
JT	JOINT TRENCH
P/PL	PROPERTY LINE
(P)	PROPOSED
PUE	PUBLIC UTILITY EASEMENT
R/W	RIGHT OF WAY
SD	STORM DRAIN
SDCI	STORM DRAIN CURB INLET
SDDI	STORM DRAIN DRAINAGE INLET
SDFI	STORM DRAIN FIELD INLET
SDJB	STORM DRAIN JUNCTION BOX
SDMH	STORM DRAIN MANHOLE
SS	SANITARY SEWER
SSCO	SANITARY SEWER CLEANOUT
SSMH	SANITARY SEWER MANHOLE
STD	STANDARD
W	WATER
WM	WATER METER
WV	WATER VALVE

LEGEND

	PROPOSED	EXISTING
PROPERTY BOUNDARY	—	—
PROPERTY LINE	—	—
RIGHT OF WAY	—	—
EASEMENT	—	—
CURB AND GUTTER	—	—
CENTERLINE	—	—
SANITARY SEWER	SS	SS(E)
SANITARY SEWER MANHOLE	●	
SANITARY LATERAL	●	
SANITARY SEWER CLEAN OUT	●	
STORM DRAIN LINE	SD	SD(E)
STORM DRAIN PERFORATED LINE	—	—
STORM DRAIN MANHOLE	○	
STORM DRAIN CLEAN OUT	●	
STORM DRAIN CURB INLET	▲	
STORM DRAIN FIELD INLET (2X2)	■	
STORM DRAIN JUNCTION BOX (2X2) W/ BOLTED DOWN SOLID COVER	■	
RETAINING WALL WITH SUBDRAIN AND WEEPHOLES. SEE DETAIL ON GRADING PLAN	—	—
TREE	●	●
FENCE	—	—
SHOWN FOR INFORMATION ONLY, DESIGNED BY OTHERS		
WATER MAIN	W	W(E)
WATER SERVICE AND METER	W	W(E)
FIRE HYDRANTS	●	
JOINT TRENCH	JT	

UTILITY PROVIDERS:

STORM DRAIN	TOWN OF LOS GATOS
SANITARY SEWER	WEST VALLEY SANITARY DISTRICT
WATER	SAN JOSE WATER CO.
GAS/ELECTRIC	PG&E




SURREY FARM ESTATES LOT 3 (S-24-025) 178 TWIN OAKS DRIVE ARCHITECTURE & SITE REVIEW

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	418510UT
CAD DWG FILE:	418510UT.LOT3.DWG
DESIGNED BY:	RH
DRAWN BY:	NW
CHECKED BY:	RH
DATE:	MAY 31, 2024
SCALE:	1" = 10'
© HMM	

UTILITY PLAN
4.0

LEGEND



2. Project Size

a. Total Site Area: 765,552 (ft ²)		b. Total Land Area Disturbed During Construction: 242,482 (ft ²) (including clearing, grading, stockpiling, or excavating)			
Project Totals	Total Existing (Pre-project) Area (ft ²)	Existing Area Retained ¹ (ft ²)	Existing Area Replaced ² (ft ²)	New Area Created ³ (ft ²)	Total Post-Project Area (ft ²)
Impervious Area (IA)					
c. Total on-site IA	0	0	0	96,692	96,692
d. Total off-site IA ⁴	694		694	0	694
e. Total project IA	694	0	694	96,692	97,386
f. Total new and replaced IA				97,386	
Pervious Area (PA)⁴					
g. Total on-site PA	764,361			667,669	
h. Total off-site PA ⁴	497			497	
i. Total project PA	764,858			668,166	
j. Total Project Area (2.e.+2.i.)	765,552			765,552	
k. Percent Replacement of IA in Redevelopment Projects: (Total Existing IA Replaced > Total Existing IA) x 100% 100 %					

¹"Retained" means to leave existing IA in place. An IA that receives surface treatment (e.g., pavement resurfacing/slurry seal/grind) only is considered "retained". This category does not apply to off-site areas.

²The "new" and "replaced" IA are based on the total project area and not specific locations within the project. Constructed IA on a project that does not exceed the total pre-project IA will be considered "replaced" IA. A project will have "new" IA only if the total post-project IA exceeds the total pre-project IA (total pre-project IA = total pre-project IA - New IA).

³Off-site areas include sidewalks and other parts of the public right-of-way (e.g., roads, bike lanes, curbs, ramps, park strip) that are being reconstructed as part of the project footprint. Do not include frontage areas that are not being reconstructed as part of the project. Note that gravel is considered an impervious surface.

⁴Include bioretention areas, infiltration areas, green roofs, and pervious pavement in PA calculations.

BIORETENTION & FLOW-THROUGH PLANTER NOTES:

- SEE GRADING PLAN FOR BASIN FOOTPRINT AND DESIGN ELEVATIONS.
- PLACE 3 INCHES OF COMPOSTED, NON-FLOATABLE MULCH IN AREAS BETWEEN STORMWATER PLANTINGS AND SIDE SLOPE.
- SEE LANDSCAPE PLAN FOR MULCH, PLANT MATERIALS AND IRRIGATION REQUIREMENTS
- CURB CUTS SHALL BE A MINIMUM 18" WIDE AND SPACED AT MAXIMUM 10' O.C. INTERVALS AND SLOPED TO DIRECT STORMWATER TO DRAIN INTO THE BASIN. CURB CUTS SHALL ALSO NOT BE PLACED INLINE WITH OVERFLOW CATCH BASIN. SEE GRADING PLAN FOR MORE DETAIL ON LOCATIONS OF CURB CUTS.
- A MINIMUM 0.2' DROP BETWEEN STORM WATER ENTRY POINT (I.E. CURB OPENING, FLUSH CURB ETC.) AND ADJACENT LANDSCAPE FINISHED GRADE.
- DO NOT COMPACT NATIVE SOIL / SUBGRADE AT BOTTOM OF BASIN. LOOSEN SOIL TO 12" DEPTH.

PERVIOUS PAVER REQUIREMENTS

CONTRACTOR OR PERMITTEE SHALL:




- PROVIDE CERTIFICATION FROM THE PAVER MANUFACTURER THAT THE PAVERS MEET THE REQUIREMENTS OF THE C3 STORMWATER HANDBOOK FOR PERVIOUS PAVERS. THIS INCLUDES, BUT IS NOT LIMITED TO, HAVING A MINIMUM SURFACE INFILTRATION RATE OF 100" /HR WHEN TESTED IN ACCORDANCE WITH ASTM C1701.
- ONLY CONTRACTORS HOLDING CERTIFICATION OF COMPLETION IN THE INTERLOCKING CONCRETE PAVEMENT INSTITUTE PCP INSTALLER TECHNICIAN COURSE SHALL BE USED TO INSTALL THE PAVERS AND AT LEAST ONE FOREMAN WITH THIS CERTIFICATION MUST BE ON THE JOBSITE AT ALL TIMES DURING CONCRETE PAVER INSTALLATION.
- PROTECT THE EXCAVATED AREA FOR PERVIOUS PAVERS FROM EXCESSIVE COMPACTION DUE TO CONSTRUCTION TRAFFIC AND PROTECT THE FINISHED PAVEMENT FROM CONSTRUCTION TRAFFIC.




STANDARD STORMWATER CONTROL NOTES:


- STANDING WATER SHALL NOT REMAIN IN THE TREATMENT MEASURES FOR MORE THAN FIVE DAYS, TO PREVENT MOSQUITO GENERATION. SHOULD ANY MOSQUITO ISSUES ARISE, CONTACT THE SANTA CLARA VALLEY VECTOR CONTROL DISTRICT (DISTRICT). MOSQUITO LARVICIDES SHALL BE APPLIED ONLY WHEN ABSOLUTELY NECESSARY, AS INDICATED BY THE DISTRICT, AND THEN ONLY BY A LICENSED PROFESSIONAL OR CONTRACTOR. CONTACT INFORMATION FOR THE DISTRICT IS PROVIDED BELOW.
- DO NOT USE PESTICIDES OR OTHER CHEMICAL APPLICATIONS TO TREAT DISEASED PLANTS, CONTROL WEEDS OR REMOVED UNWANTED GROWTH. EMPLOY NON-CHEMICAL CONTROLS (BIOLOGICAL, PHYSICAL AND CULTURAL CONTROLS) TO TREAT A PEST PROBLEM. PRUNE PLANTS PROPERLY AND AT THE APPROPRIATE TIME OF YEAR. PROVIDE ADEQUATE IRRIGATION FOR LANDSCAPE PLANTS. DO NOT OVER WATER.

HYDROMODIFICATION NOTE:

- REFER TO THE "SUMMARY OF BAHM MODELING FOR THE SURVEY FARM PROJECT" REPORT FOR HYDROMODIFICATION AND STORMWATER TREATMENT DESIGN ASSUMPTIONS AND SUMMARY OF RESULTS.



<p>PROJECT SITE INFORMATION:</p> <p>1. SOILS TYPE: C (SANDY LOAM) 2. GROUND WATER DEPTH: 30' - 50' 3. NAME OF RECEIVING BODY: GUADALUPE CREEK 4. FLOOD ZONE: X 5. FLOOD ELEVATION (IF APPLICABLE): N/A</p>	<p>SOURCE CONTROL MEASURES:</p> <p>1. BENEFICIAL LANDSCAPING 2. MAINTENANCE (PAVEMENT SWEEPING, CATCH BASIN CLEANING, GOOD HOUSEKEEPING) 3. STORM DRAIN LABELING.</p>	<p>BIOTREATMENT SOIL REQUIREMENTS</p> <p>BIORETENTION SOIL MIX SHALL MEET THE REQUIREMENTS AS OUTLINED IN APPENDIX C OF THE C.3 STORM WATER HANDBOOK AND SHALL BE A MIXTURE OF FINE SAND AND COMPOST MEASURED ON A VOLUME BASIS OF 60-70% SAND AND 30-40% COMPOST. CONTRACTOR TO REFER TO APPENDIX C FOR SAND AND COMPOST MATERIAL SPECIFICATIONS. CONTRACTOR MAY OBTAIN A COPY OF THE C3 HANDBOOK AT HTTPS://CLEANWATER.SCCGOV.ORG/SITES/G/FILES/EXJCP8461/FILES/SCVURPPP_C.PDF</p> <p>PRIOR TO ORDERING THE BIOTREATMENT SOIL MIX OR DELIVERY TO THE PROJECT SITE, CONTRACTOR SHALL PROVIDE A BIOTREATMENT SOIL MIX SPECIFICATION CHECKLIST, COMPLETED BY THE SOIL MIX SUPPLIER AND CERTIFIED TESTING LAB.</p>	<p>TABLE 1 ROUTINE MAINTENANCE ACTIVITIES FOR BIORETENTION AREAS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>NO.</th> <th>MAINTENANCE TASK</th> <th>FREQUENCY OF TASK</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>REMOVE OBSTRUCTIONS, WEEDS, DEBRIS AND TRASH FROM BIORETENTION AREA AND ITS INLETS AND OUTLETS; AND DISPOSE OF PROPERLY.</td> <td>QUARTERLY, OR AS NEEDED AFTER STORM EVENTS</td> </tr> <tr> <td>2</td> <td>INSPECT BIORETENTION AREA FOR STANDING WATER. IF STANDING WATER DOES NOT DRAIN WITHIN 2-3 DAYS, TILL AND REPLACE THE SURFACE BIOTREATMENT SOIL WITH THE APPROVED SOIL MIX AND REPLANT.</td> <td>QUARTERLY, OR AS NEEDED AFTER STORM EVENTS</td> </tr> <tr> <td>3</td> <td>CHECK UNDERDRAINS FOR CLOGGING. USE THE CLEANOUT RISER TO CLEAN ANY CLOGGED UNDERDRAINS.</td> <td>QUARTERLY, OR AS NEEDED AFTER STORM EVENTS</td> </tr> <tr> <td>4</td> <td>MAINTAIN THE IRRIGATION SYSTEM AND ENSURE THAT PLANTS ARE RECEIVING THE CORRECT AMOUNT OF WATER (IF APPLICABLE).</td> <td>QUARTERLY</td> </tr> <tr> <td>5</td> <td>ENSURE THAT THE VEGETATION IS HEALTHY AND DENSE ENOUGH TO PROVIDE FILTERING AND PROTECT SOILS FROM EROSION. PRUNE AND WEED THE BIORETENTION AREA. REMOVE AND/OR REPLACE ANY DEAD PLANTS.</td> <td>ANNUALLY, BEFORE THE WET SEASON BEGINS</td> </tr> <tr> <td>6</td> <td>USE COMPOST AND OTHER NATURAL SOIL AMENDMENTS AND FERTILIZERS INSTEAD OF SYNTHETIC FERTILIZERS, ESPECIALLY IF THE SYSTEM USES AN UNDERDRAIN.</td> <td>ANNUALLY, BEFORE THE WET SEASON BEGINS</td> </tr> <tr> <td>7</td> <td>CHECK THAT MULCH IS AT APPROPRIATE DEPTH (2 - 3 INCHES PER SOIL SPECIFICATIONS) AND REPLENISH AS NECESSARY BEFORE WET SEASON BEGINS. IT IS RECOMMENDED THAT 2" - 3" OF ARBOR MULCH BE REAPPLIED EVERY YEAR.</td> <td>ANNUALLY, BEFORE THE WET SEASON BEGINS</td> </tr> <tr> <td>8</td> <td>INSPECT THE ENERGY DISSIPATION AT THE INLET TO ENSURE IT IS FUNCTIONING ADEQUATELY, AND THAT THERE IS NO SCOUR OF THE SURFACE MULCH. REMOVE ACCUMULATED SEDIMENT.</td> <td>ANNUALLY, BEFORE THE WET SEASON BEGINS</td> </tr> <tr> <td>9</td> <td>INSPECT OVERFLOW PIPE TO ENSURE THAT IT CAN SAFELY CONVEY EXCESS FLOWS TO A STORM DRAIN. REPAIR OR REPLACE DAMAGED PIPING.</td> <td>ANNUALLY, BEFORE THE WET SEASON BEGINS</td> </tr> <tr> <td>10</td> <td>REPLACE BIOTREATMENT SOIL AND MULCH, IF NEEDED. CHECK FOR STANDING WATER, STRUCTURAL FAILURE AND CLOGGED OVERFLOWS. REMOVE TRASH AND DEBRIS. REPLACE DEAD PLANTS.</td> <td>ANNUALLY, BEFORE THE WET SEASON BEGINS</td> </tr> <tr> <td>11</td> <td>INSPECT BIORETENTION AREA USING THE ATTACHED INSPECTION CHECKLIST.</td> <td>ANNUALLY, BEFORE THE WET SEASON</td> </tr> </tbody> </table>	NO.	MAINTENANCE TASK	FREQUENCY OF TASK	1	REMOVE OBSTRUCTIONS, WEEDS, DEBRIS AND TRASH FROM BIORETENTION AREA AND ITS INLETS AND OUTLETS; AND DISPOSE OF PROPERLY.	QUARTERLY, OR AS NEEDED AFTER STORM EVENTS	2	INSPECT BIORETENTION AREA FOR STANDING WATER. IF STANDING WATER DOES NOT DRAIN WITHIN 2-3 DAYS, TILL AND REPLACE THE SURFACE BIOTREATMENT SOIL WITH THE APPROVED SOIL MIX AND REPLANT.	QUARTERLY, OR AS NEEDED AFTER STORM EVENTS	3	CHECK UNDERDRAINS FOR CLOGGING. USE THE CLEANOUT RISER TO CLEAN ANY CLOGGED UNDERDRAINS.	QUARTERLY, OR AS NEEDED AFTER STORM EVENTS	4	MAINTAIN THE IRRIGATION SYSTEM AND ENSURE THAT PLANTS ARE RECEIVING THE CORRECT AMOUNT OF WATER (IF APPLICABLE).	QUARTERLY	5	ENSURE THAT THE VEGETATION IS HEALTHY AND DENSE ENOUGH TO PROVIDE FILTERING AND PROTECT SOILS FROM EROSION. PRUNE AND WEED THE BIORETENTION AREA. REMOVE AND/OR REPLACE ANY DEAD PLANTS.	ANNUALLY, BEFORE THE WET SEASON BEGINS	6	USE COMPOST AND OTHER NATURAL SOIL AMENDMENTS AND FERTILIZERS INSTEAD OF SYNTHETIC FERTILIZERS, ESPECIALLY IF THE SYSTEM USES AN UNDERDRAIN.	ANNUALLY, BEFORE THE WET SEASON BEGINS	7	CHECK THAT MULCH IS AT APPROPRIATE DEPTH (2 - 3 INCHES PER SOIL SPECIFICATIONS) AND REPLENISH AS NECESSARY BEFORE WET SEASON BEGINS. IT IS RECOMMENDED THAT 2" - 3" OF ARBOR MULCH BE REAPPLIED EVERY YEAR.	ANNUALLY, BEFORE THE WET SEASON BEGINS	8	INSPECT THE ENERGY DISSIPATION AT THE INLET TO ENSURE IT IS FUNCTIONING ADEQUATELY, AND THAT THERE IS NO SCOUR OF THE SURFACE MULCH. REMOVE ACCUMULATED SEDIMENT.	ANNUALLY, BEFORE THE WET SEASON BEGINS	9	INSPECT OVERFLOW PIPE TO ENSURE THAT IT CAN SAFELY CONVEY EXCESS FLOWS TO A STORM DRAIN. REPAIR OR REPLACE DAMAGED PIPING.	ANNUALLY, BEFORE THE WET SEASON BEGINS	10	REPLACE BIOTREATMENT SOIL AND MULCH, IF NEEDED. CHECK FOR STANDING WATER, STRUCTURAL FAILURE AND CLOGGED OVERFLOWS. REMOVE TRASH AND DEBRIS. REPLACE DEAD PLANTS.	ANNUALLY, BEFORE THE WET SEASON BEGINS	11	INSPECT BIORETENTION AREA USING THE ATTACHED INSPECTION CHECKLIST.	ANNUALLY, BEFORE THE WET SEASON																																																																																																										
NO.	MAINTENANCE TASK	FREQUENCY OF TASK																																																																																																																																															
1	REMOVE OBSTRUCTIONS, WEEDS, DEBRIS AND TRASH FROM BIORETENTION AREA AND ITS INLETS AND OUTLETS; AND DISPOSE OF PROPERLY.	QUARTERLY, OR AS NEEDED AFTER STORM EVENTS																																																																																																																																															
2	INSPECT BIORETENTION AREA FOR STANDING WATER. IF STANDING WATER DOES NOT DRAIN WITHIN 2-3 DAYS, TILL AND REPLACE THE SURFACE BIOTREATMENT SOIL WITH THE APPROVED SOIL MIX AND REPLANT.	QUARTERLY, OR AS NEEDED AFTER STORM EVENTS																																																																																																																																															
3	CHECK UNDERDRAINS FOR CLOGGING. USE THE CLEANOUT RISER TO CLEAN ANY CLOGGED UNDERDRAINS.	QUARTERLY, OR AS NEEDED AFTER STORM EVENTS																																																																																																																																															
4	MAINTAIN THE IRRIGATION SYSTEM AND ENSURE THAT PLANTS ARE RECEIVING THE CORRECT AMOUNT OF WATER (IF APPLICABLE).	QUARTERLY																																																																																																																																															
5	ENSURE THAT THE VEGETATION IS HEALTHY AND DENSE ENOUGH TO PROVIDE FILTERING AND PROTECT SOILS FROM EROSION. PRUNE AND WEED THE BIORETENTION AREA. REMOVE AND/OR REPLACE ANY DEAD PLANTS.	ANNUALLY, BEFORE THE WET SEASON BEGINS																																																																																																																																															
6	USE COMPOST AND OTHER NATURAL SOIL AMENDMENTS AND FERTILIZERS INSTEAD OF SYNTHETIC FERTILIZERS, ESPECIALLY IF THE SYSTEM USES AN UNDERDRAIN.	ANNUALLY, BEFORE THE WET SEASON BEGINS																																																																																																																																															
7	CHECK THAT MULCH IS AT APPROPRIATE DEPTH (2 - 3 INCHES PER SOIL SPECIFICATIONS) AND REPLENISH AS NECESSARY BEFORE WET SEASON BEGINS. IT IS RECOMMENDED THAT 2" - 3" OF ARBOR MULCH BE REAPPLIED EVERY YEAR.	ANNUALLY, BEFORE THE WET SEASON BEGINS																																																																																																																																															
8	INSPECT THE ENERGY DISSIPATION AT THE INLET TO ENSURE IT IS FUNCTIONING ADEQUATELY, AND THAT THERE IS NO SCOUR OF THE SURFACE MULCH. REMOVE ACCUMULATED SEDIMENT.	ANNUALLY, BEFORE THE WET SEASON BEGINS																																																																																																																																															
9	INSPECT OVERFLOW PIPE TO ENSURE THAT IT CAN SAFELY CONVEY EXCESS FLOWS TO A STORM DRAIN. REPAIR OR REPLACE DAMAGED PIPING.	ANNUALLY, BEFORE THE WET SEASON BEGINS																																																																																																																																															
10	REPLACE BIOTREATMENT SOIL AND MULCH, IF NEEDED. CHECK FOR STANDING WATER, STRUCTURAL FAILURE AND CLOGGED OVERFLOWS. REMOVE TRASH AND DEBRIS. REPLACE DEAD PLANTS.	ANNUALLY, BEFORE THE WET SEASON BEGINS																																																																																																																																															
11	INSPECT BIORETENTION AREA USING THE ATTACHED INSPECTION CHECKLIST.	ANNUALLY, BEFORE THE WET SEASON																																																																																																																																															
<p>OPERATION AND MAINTENANCE INFORMATION:</p> <p>I. PROPERTY INFORMATION: I.A. PROPERTY ADDRESS: 178 TWIN OAKS DRIVE LOS GATOS, CA, 95032</p> <p>I.B. PROPERTY OWNER: JEFFREY L DODGE EXEMPT TRUST</p> <p>II. RESPONSIBLE PARTY FOR MAINTENANCE: II.A. CONTACT: LARRY DODGE</p> <p>II.B. PHONE NUMBER OF CONTACT: 858-243-7768</p> <p>II.C. EMAIL: ldodge@gmail.com</p> <p>II.D. ADDRESS: PO BOX 2029 RANCHO SANTA FE, CA 92067</p>	<p>SITE DESIGN MEASURES:</p> <p>1. MINIMIZE LAND DISTURBED 2. MINIMUM-IMPACT STREET OR PARKING LOT DESIGN 3. PERVIOUS PAVEMENT 4. OTHER SELF-TREATING AREA 5. PRESERVE OPEN SPACE 6. PROTECTED RIPARIAN AND WETLAND AREAS/BUFFERS</p>	<p>Drainage Management Area (DMA) Summary Table Complete the information below at the Building Permit stage for Regulated C3 Projects and Non-Regulated Green Stormwater Infrastructure Projects</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Project Name</th> <th>APN #</th> <th>Project Address:</th> <th>Cross Streets:</th> </tr> </thead> <tbody> <tr> <td>Surrey Farm Estates</td> <td>532-16-006</td> <td>Twin Oaks Drive, Los Gatos</td> <td>Longmeadow Drive</td> </tr> </tbody> </table> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Drainage Area #</th> <th>Impervious Area (ft²)</th> <th>Pervious Area (ft²)</th> <th>Site Design Measures or Stormwater Treatment Measures</th> <th>Hydraulic Sizing Criteria Used</th> </tr> </thead> <tbody> <tr> <td>A</td> <td>1233</td> <td>31502</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>AA</td> <td>694</td> <td>0</td> <td></td> <td>Not Applicable</td> </tr> <tr> <td>B</td> <td>0</td> <td>310011</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B1</td> <td>3852</td> <td>6148</td> <td>Self-retaining areas</td> <td>Not Applicable</td> </tr> <tr> <td>B1A</td> <td>0</td> <td>5570</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B1B</td> <td>0</td> <td>65296</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B2</td> <td>5191</td> <td>2662</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>B2A</td> <td>0</td> <td>999</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B3</td> <td>5320</td> <td>2126</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>B3A</td> <td>0</td> <td>1926</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B3B</td> <td>0</td> <td>4839</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B3C</td> <td>0</td> <td>4886</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B4</td> <td>6809</td> <td>6595</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>B5+6</td> <td>31608</td> <td>10762</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>B7</td> <td>8946</td> <td>3084</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>B7A</td> <td>0</td> <td>11272</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B7B</td> <td>0</td> <td>55461</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B8</td> <td>8938</td> <td>723</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>B9</td> <td>8936</td> <td>2667</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>B9A</td> <td>0</td> <td>24762</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B10</td> <td>10155</td> <td>2995</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>B10A</td> <td>0</td> <td>2945</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>B10B</td> <td>0</td> <td>4856</td> <td>Self-treating areas</td> <td></td> </tr> <tr> <td>B11</td> <td>5704</td> <td>1772</td> <td>Bioretention area - lined* with underdrain</td> <td>3: Combination Flow and Volume Design Method</td> </tr> <tr> <td>C</td> <td>0</td> <td>104307</td> <td>Self-treating areas</td> <td>Not Applicable</td> </tr> <tr> <td>TOTAL</td> <td>97386</td> <td>668166</td> <td></td> <td></td> </tr> </tbody> </table>	Project Name	APN #	Project Address:	Cross Streets:	Surrey Farm Estates	532-16-006	Twin Oaks Drive, Los Gatos	Longmeadow Drive	Drainage Area #	Impervious Area (ft ²)	Pervious Area (ft ²)	Site Design Measures or Stormwater Treatment Measures	Hydraulic Sizing Criteria Used	A	1233	31502	Self-treating areas	Not Applicable	AA	694	0		Not Applicable	B	0	310011	Self-treating areas	Not Applicable	B1	3852	6148	Self-retaining areas	Not Applicable	B1A	0	5570	Self-treating areas	Not Applicable	B1B	0	65296	Self-treating areas	Not Applicable	B2	5191	2662	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	B2A	0	999	Self-treating areas	Not Applicable	B3	5320	2126	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	B3A	0	1926	Self-treating areas	Not Applicable	B3B	0	4839	Self-treating areas	Not Applicable	B3C	0	4886	Self-treating areas	Not Applicable	B4	6809	6595	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	B5+6	31608	10762	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	B7	8946	3084	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	B7A	0	11272	Self-treating areas	Not Applicable	B7B	0	55461	Self-treating areas	Not Applicable	B8	8938	723	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	B9	8936	2667	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	B9A	0	24762	Self-treating areas	Not Applicable	B10	10155	2995	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	B10A	0	2945	Self-treating areas	Not Applicable	B10B	0	4856	Self-treating areas		B11	5704	1772	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method	C	0	104307	Self-treating areas	Not Applicable	TOTAL	97386	668166		
Project Name	APN #	Project Address:	Cross Streets:																																																																																																																																														
Surrey Farm Estates	532-16-006	Twin Oaks Drive, Los Gatos	Longmeadow Drive																																																																																																																																														
Drainage Area #	Impervious Area (ft ²)	Pervious Area (ft ²)	Site Design Measures or Stormwater Treatment Measures	Hydraulic Sizing Criteria Used																																																																																																																																													
A	1233	31502	Self-treating areas	Not Applicable																																																																																																																																													
AA	694	0		Not Applicable																																																																																																																																													
B	0	310011	Self-treating areas	Not Applicable																																																																																																																																													
B1	3852	6148	Self-retaining areas	Not Applicable																																																																																																																																													
B1A	0	5570	Self-treating areas	Not Applicable																																																																																																																																													
B1B	0	65296	Self-treating areas	Not Applicable																																																																																																																																													
B2	5191	2662	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
B2A	0	999	Self-treating areas	Not Applicable																																																																																																																																													
B3	5320	2126	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
B3A	0	1926	Self-treating areas	Not Applicable																																																																																																																																													
B3B	0	4839	Self-treating areas	Not Applicable																																																																																																																																													
B3C	0	4886	Self-treating areas	Not Applicable																																																																																																																																													
B4	6809	6595	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
B5+6	31608	10762	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
B7	8946	3084	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
B7A	0	11272	Self-treating areas	Not Applicable																																																																																																																																													
B7B	0	55461	Self-treating areas	Not Applicable																																																																																																																																													
B8	8938	723	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
B9	8936	2667	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
B9A	0	24762	Self-treating areas	Not Applicable																																																																																																																																													
B10	10155	2995	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
B10A	0	2945	Self-treating areas	Not Applicable																																																																																																																																													
B10B	0	4856	Self-treating areas																																																																																																																																														
B11	5704	1772	Bioretention area - lined* with underdrain	3: Combination Flow and Volume Design Method																																																																																																																																													
C	0	104307	Self-treating areas	Not Applicable																																																																																																																																													
TOTAL	97386	668166																																																																																																																																															
<p>*"Lined" refers to an impermeable liner placed on the bottom of a bioretention area, such that no infiltration into native soil occurs.</p>																																																																																																																																																	
 <p>2" NO. 8 AGGREGATE BEDDING COURSE 4" NO. 57 STONE 6" MIN. NO 2 STONE SUBBASE 20" MIN. NO. 57 STONE 6" MIN. NO 2 STONE SUBBASE 4" MIN. NO. 57 STONE 6" VERTICAL CURB OR FLUSH CONCRETE HEADER PERVIOUS CONCRETE PAVERS 3-1/8" THICK TYP. NO. 8 AGGREGATE IN OPENINGS OPTIONAL GEOTEXTILE ON BOTTOM AND SIDES OF OPEN-GRADED BASE FLAT BOTTOM TOS ELEVATION PERFORATED PIPE (SLOPE AT 0.50% MIN) W/ PERFORATIONS DOWN. SEE PLAN FOR LENGTH AND LOCATION. STORAGE DEPTH 12" MIN NOTE: MINIMUM STORAGE DEPTH OF 12" IS PROVIDED FOR HYDROMODIFICATION. FLAT BOTTOM TOP OF SUBGRADE (TOS)</p>	 <p>BIOPOND INSTALL 24" WIDE APRON OF 4" COBBLES AROUND BUBBLER RIM V 12 CHRISTY BOX WITH OPEN GRATE SEE PLAN FOR RIM ELEVATION OVERFLOW RISER W/GRATE IMPEERABLE LINER ALONG VERTICAL EDGE PLACE GEOTEXTILE BETWEEN COBBLES & NATIVE SOIL FOR EROSION CONTROL CONTRACTOR TO DRILL 2 ROWS OF (2) 2" DIA. WEEPHOLES DRAIN ROCK TO BE LINED WITH 20-MIL HDPE WATER BARRIER ALONG VERTICAL EDGE WITH A 2" WRAP OPEN TO DRAIN</p>	 <p>IF NATIVE MATERIAL IS USED FOR SIDESLOPE, RELATIVE COMPACTION OF SUBGRADE TO BE SIMILAR TO ADJOINING NATIVE SOILS 1 SIDE SLOPE 3 MAX. SLOPE VARIES 6" RISER HEIGHT CLEANOUT W/ CAP AT FINISH GRADE CHRISTY V12 OR APPROVED EQUAL OVERFLOW RISER W/ GRATE SLOPE VARIES BIO-TREATMENT SOIL MIX (BSM) PER SPECS. 24" MIN. OF CLASS II PERMEABLE ROCK PER CALTRANS SPECS. ROCK SECTION TO INCREASE IF PERFORATED PIPE REACHES BOTTOM OF 24" SECTION PERFORATED PIPE (SLOPE AT 0.50% MIN) W/ PERFORATIONS DOWN. SEE PLAN FOR LENGTH AND LOCATION. NATIVE MATERIAL SOLID OVERFLOW PIPE SIZING METHOD: FLOW-COMBO</p>																																																																																																																																															
<p>3 PERVIOUS PAVEMENT (SELF RETAINING OR SELF TREATING) N.T.S.</p>	<p>2 BUBBLER BOX DETAIL N.T.S.</p>	<p>1 BIOPRETENTION BASIN W/ LINER N.T.S.</p>																																																																																																																																															



EROSION AND SEDIMENT CONTROL NOTES

1. CONTRACTOR/OWNER:
JEFF CURRAN
1475 SARATOGA AVENUE
SAN JOSE, CA 95129
(408) 252-9131

IT SHALL BE THE OWNER'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THE SOIL EROSION CONTROL PLAN.
2. CIVIL ENGINEER:
HMH ENGINEERS
1570 OAKLAND ROAD
SAN JOSE, CA 95131
ATTN: RAFAEL HERNANDEZ
408 487 2200
3. THIS PLAN IS INTENDED TO BE USED FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY AND IS NOT TO BE USED FOR FINAL ELEVATIONS OR PERMANENT IMPROVEMENTS.
4. IT IS THE RESPONSIBILITY OF THE OWNER/CONTRACTOR TO ENSURE THAT NO MUD OR SILTATION LEAVES THE PROJECT SITE.
5. INTERIM EROSION CONTROL MEASURES MUST BE COMPLETED AND IN PLACE BY OCTOBER 1.
6. ALL INTERIM EROSION CONTROL MEASURES MUST BE CONTINUOUSLY MAINTAINED THROUGHOUT THE OCTOBER 1 TO APRIL 15 RAINY SEASON.
7. CALL THE INSPECTION LINE AT (408) 399-5760 BY SEPTEMBER 15 FOR INSPECTION OF EROSION CONTROL DEVICES. CALL 24 HOURS IN ADVANCE. INCLUDE GRADING PERMIT NUMBER.
8. IF EROSION CONTROL MEASURES ARE NOT IN PLACE AS REQUIRED OR NOT MAINTAINED, ALL WORK SHALL CEASE UNTIL EROSION CONTROL MEASURES ARE REMEDIED.

BUILDING PAD PROTECTION NOTE:

1. IF PAD WILL REMAIN WITHOUT BUILDING CONSTRUCTION DURING THE RAINY SEASON, THE PAD SHALL BE STABILIZED OR PROVIDED WITH AN EROSION BLANKET TO PROTECT THE BUILDING PAD.

EROSION CONTROL PLAN NOTE:


THIS WATER POLLUTION CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES (BMPs) LISTED IN THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP), AND SHALL IMPLEMENT AND MAINTAIN THE SWPPP FOR THE PROJECT IN FULL COMPLIANCE WITH THE REVISED STATE REGULATIONS TO CONTROL THE DISCHARGE OF STORMWATER POLLUTANTS.

LEGEND

- STANDARD INLET PROTECTION
- FIBER ROLL OR SILT FENCE (SEE PLAN)
- STABILIZED CONSTRUCTION ENTRANCE
- HYDROSEED DISTURBED AREA

MAINTENANCE SCHEDULE

CONTROL	INSPECTION FREQUENCY	MAINTENANCE/REPAIR MEASURES
STABILIZED CONSTRUCTION ENTRANCE	WEEKLY & AFTER EACH RAIN	REPLACE GRAVEL MATERIAL WHEN Voids ARE PRESENT REMOVE ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS WITHIN 24 HOURS REMOVE GRAVEL AT COMPLETION OF CONSTRUCTION
STORM DRAIN INLET PROTECTION	WEEKLY & AFTER EACH RAIN	REPLACE CLOGGED FILTER FABRIC IMMEDIATELY REMOVE SEDIMENT WHEN IT REACHES 1/2 THE HEIGHT OF THE FILTER
SEDIMENT BASIN	WEEKLY & AFTER EACH RAIN	REMOVE SEDIMENT WHEN THE SEDIMENT STORAGE ZONE IS HALF FULL REPAIR EROSION AS NECESSARY UNCLOG OUTLET RISER
HYDROSEED/HYDROMULCH EROSION CONTROL BLANKETS	PERIODICALLY DURING & AFTER EACH RAIN	PRIOR TO RESEEDING, REPAIR ALL RILLS AND GULLIES REMOVE SEDIMENT BUILDUP AT TOE OF SLOPES REAPPLY SEED AND/OR MULCH TO AREAS THAT HAVE BEEN REPAIRED, ERODED, OR ARE WITHOUT ADEQUATE VEGETATION DISLOCATED BLANKETS, NETS, OR MATS SHOULD BE REPAIRED OR REPLACED
STRAW ROLLS	WEEKLY & AFTER EACH RAIN	REPAIR WHENEVER STRAW ROLL IS DAMAGED REMOVE SEDIMENT WHEN IT REACHES 1/3 THE HEIGHT OF THE ROLLS ESPECIALLY IF HEAVY RAINS ARE EXPECTED




SURREY FARM ESTATES
LOT 3 (S-24-025)
178 TWIN OAKS DRIVE
ARCHITECTURE & SITE REVIEW

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	418510
CAD DWG FILE:	418510EC_Lot3.DWG
DESIGNED BY:	AV/RH
DRAWN BY:	AV
CHECKED BY:	RH
DATE:	MAY 31ST, 2024
SCALE:	1" = 50'
(C) HMH	

EROSION CONTROL PLAN

6.0



SURREY FARM ESTATES


LOT 3 (S-24-025)

178 TWIN OAKS DRIVE

ARCHITECTURE & SITE REVIEW

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	4185.10
CAD DWG FILE:	418510EC.LOT3.DWG
DESIGNED BY:	AV/RH
DRAWN BY:	NW
CHECKED BY:	RH
DATE:	MAY 31ST, 2024
SCALE:	NOT TO SCALE
(C) HMH	

EROSION CONTROL DETAILS



SURREY FARM ESTATES

LOT 3 (S-24-025)

178 TWIN OAKS DRIVE

ARCHITECTURE & SITE REVIEW

6'x6' ANCHOR TRENCH
MATS / BLANKETS SHOULD BE INSTALLED DOWNSLOPE
BERM
TAMP DIRT OVER MATS / BLANKETS
2:1 (H/V) SLOPE MAX
12°
FILTER CLOTH 4" ABOVE SOURCE OF WATER
WATER TABLE
NON-WOVEN GEOTEXTILE FILTER FABRIC UNDER TYPICAL TREATMENT
ISOMETRIC VIEW
TYPICAL SLOPE SOIL STABILIZATION
N.T.S.
NOTES:
1. SLOPE SURFACES SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS. MATS / BLANKETS SHALL HAVE GOOD SOIL CONTACT
2. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH
3. INSTALL PER MANUFACTURER'S RECOMMENDATIONS

EC-7 GEOTEXTILES AND MATS TYPICAL INSTALLATION DETAIL
N.T.S.

NOTE: SIZE SPILLWAY TO CONVEY PEAK DESIGN FLOW
TYPICAL OPEN SPILLWAY
OUTLET PIPE OR USE ALTERNATIVE OPEN SPILLWAY
EXCAVATE IF NECESSARY FOR STORAGE
FLOW
EARTH EMBANKMENT
OUTLET PROTECTION
NOTES:
1. OUTLET PIPE OR USE ALTERNATIVE OPEN SPILLWAY
2. EXCAVATE IF NECESSARY FOR STORAGE
3. FLOW

ALL SLOPE 1:3 (V:H) OR FLATTER
5'-0" MIN
12° MIN
PERFORATE RISER
WATERTIGHT CONNECTION
NOTES:
1. ALL SLOPE 1:3 (V:H) OR FLATTER
2. 5'-0" MIN
3. 12° MIN
4. PERFORATE RISER
5. WATERTIGHT CONNECTION

SE-3 SEDIMENT TRAP
N.T.S.

INITIAL CHANNEL ANCHOR TRENCH
N.T.S.
TERMINAL SLOPE AND CHANNEL ANCHOR TRENCH
N.T.S.
STAKE AT 3' TO 5' INTERVALS
3' OVERLAP
STAPLE SPACING IN SLOPES 12"
CHECK SLOT AT 25'-30' INTERVALS
ISOMETRIC VIEW
N.T.S.
INTERMITTENT CHECK SLOT
N.T.S.
LONGITUDINAL ANCHOR TRENCH
N.T.S.

EC-7 GEOTEXTILES AND MATS TYPICAL INSTALLATION DETAIL
N.T.S.

FIBER ROLLS
NOTE: INSTALL FIBER ROLL ALONG A LEVEL CONTOUR
4' MAX
4' MAX
4' MAX
VERTICAL SPACING MEASURED ALONG THE FACE OF THE SLOPE VARIES BETWEEN 10' AND 20'
INSTALL FIBER ROLL NEAR SLOPE WHERE IT TRANSITIONS INTO A STEEPER SLOPE
FIBER ROLL INSTALLATION
N.T.S.

SE-5 FIBER ROLLS
N.T.S.

OPTIONAL MAINTENANCE OPENING DETAIL
WOOD STAKE
FABRIC
END DETAIL
SLOPE
TOE OF SLOPE
CROSS BARRIER (SEE NOTE 10)
SILT FENCE PLAN
N.T.S.
SILT FENCE
END DETAIL
SILT FENCE FABRIC
END STAKE (SEE NOTE 2)
SILT FENCE
END DETAIL
OPTIONAL MAINTENANCE OPENING DETAIL
DETAIL A
FABRIC
STAKE
SANDBAGS TWO LAYERS HIGH
END STAKE
SLOPE
TOP OF SLOPE
SILT FENCE FABRIC
END DETAIL
JOINING SECTION DETAIL (TOP VIEW)
FABRIC SECTION A (SEE NOTES 6, 7 & 12)
STAKE B
FABRIC SECTION B (SEE NOTES 6, 7 & 12)
STAKE A
SANDBAGS
SEE NOTE 10
SECTION C-C
N.T.S.
SECTION A-A
SETBACK VARIES (SEE NOTE 4)
2"x2" WOOD STAKE (SEE NOTE 3 & 5)
FABRIC
SEE DETAIL A
TOE OF SLOPE
SLOPE
CROSS BARRIER DETAIL
N.T.S.
END STAKE DETAIL (TOP VIEW)
FABRIC (SEE NOTE 8)
2"x2" WOOD STAKE (SEE NOTE 3)
SILT FENCE
C
C
TOE OF SLOPE
SLOPE

NOTES:
1. CONSTRUCT LENGTH OF EACH REACH SO THAT THE CHANGE IN BASE ELEVATION ALONG THE REACH DOES NOT EXCEED 1/3 THE HEIGHT OF THE LINEAR BARRIER IN NO CASE SHALL THE REACH LENGTH EXCEED 500'
2. THE LAST 8'-0" OF FENCE SHALL BE TURNED UP SLOPE
3. STAKE DIMENSIONS ARE NOMINAL
4. DIMENSION MAY VARY TO FIT FIELD CONDITIONS
5. STAKES SHALL BE SPACED AT 8'-0" MAXIMUM AND SHALL BE POSITIONED ON THE DOWNSIDE OF THE FENCE
6. STAKES TO OVERLAP AND FENCE FABRIC TO FOLD AROUND EACH STAKE ONE FULL TURN. SECURE FABRIC TO STAKE WITH 4 STAPLES
7. STAKES SHALL BE DRIVEN LIGHTLY TOGETHER TO PREVENT POTENTIAL FLOW-THROUGH OF SEDIMENT AT JOINT. THE TOPS OF THE STAKES SHALL BE SECURED WITH WIRE
8. FOR END STAKE FENCE FABRIC SHALL BE FOLDED AROUND TWO STAKES ONE FULL TURN AND SECURED WITH 4 STAPLES
9. MINIMUM 4 STAPLES PER STAKE. DIMENSIONS SHOWN ARE TYPICAL
10. CROSS BARRIERS SHALL BE A MINIMUM OF 1/3 AND A MAXIMUM OF 1/2 HEIGHT OF THE LINEAR BARRIER
11. MAINTENANCE OPENINGS SHALL BE CONSTRUCTED IN A MANNER TO ENSURE SEDIMENT REMAINS BEHIND SILT FENCE
12. JOINING SECTIONS SHALL NOT BE PLACED AT SUMP LOCATIONS
13. SANDBAG ROWS AND LAYERS SHALL BE OFFSET TO ELIMINATE GAPS

SE-1 SILT FENCE
N.T.S.

EROSION CONTROL PLAN NOTES:

THIS WATER POLLUTION CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES (BMPs) LISTED IN THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP), AND SHALL IMPLEMENT AND MAINTAIN THE SWPPP FOR THE PROJECT IN FULL COMPLIANCE WITH THE REVISED STATE REGULATIONS TO CONTROL THE DISCHARGE OF STORMWATER POLLUTANTS.

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
NO	DATE
PROJECT NO:	418510
CAD DWG FILE:	418510EC.LOT3.DWG
DESIGNED BY:	XX
DRAWN BY:	J2WQ
CHECKED BY:	XX
DATE:	MAY 31ST, 2024
SCALE:	AS SHOWN
(C)	HMH

EROSION CONTROL DETAILS


NOTE:
DETAILS SHOWN ARE BASED UPON THE CALIFORNIA STORMWATER QUALITY ASSOCIATION'S STORMWATER BEST MANAGEMENT PRACTICE HANDBOOK.

6.3

PLOTTED: 10/20/2025 2:18 PM

PROJECT TS418510EC.LOT3 PERMIT#418510EC.LOT3

Pollution Prevention — It's Part of the Plan



Materials storage & spill cleanup

Non-hazardous materials management

- ✓ Sand, dirt, and similar materials must be stored at least 10 feet from catch basins, and covered with a tarp during wet weather or when rain is forecast.
- ✓ Use (but don't overuse) reclaimed water for dust control as needed.
- ✓ Sweep streets and other paved areas daily. Do not wash down streets or work areas with water!
- ✓ Recycle all asphalt, concrete, and aggregate base material from demolition activities.
- ✓ Check dumpsters regularly for leaks and to make sure they don't overflow. Repair or replace leaking dumpsters promptly.

Hazardous materials management

- ✓ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, state, and federal regulations.
- ✓ Store hazardous materials and wastes in secondary containment and cover them during wet weather.
- ✓ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ✓ Be sure to arrange for appropriate disposal of all hazardous wastes.

Spill prevention and control

- ✓ Keep a stockpile of spill cleanup materials (rags, absorbents, etc.) available at the construction site at all times.
- ✓ When spills or leaks occur, contain them immediately and be particularly careful to prevent leaks and spills from reaching the gutter, street, or storm drain. Never wash spilled material into a gutter, street, storm drain, or creek!
- ✓ Report any hazardous materials spills immediately! Dial 911 or your local emergency response number.

Make sure your crews and subs do the job right!

Runoff from streets and other paved areas is a major source of pollution in San Francisco Bay. Construction activities can directly affect the health of the Bay unless contractors and crews plan ahead to keep dirt, debris, and other construction waste away from storm drains and local creeks. Following these guidelines will ensure your compliance with local ordinance requirements.

Vehicle and equipment maintenance & cleaning



- ✓ Inspect vehicles and equipment for leaks frequently. Use drip pans to catch leaks until repairs are made; repair leaks promptly.
- ✓ Fuel and maintain vehicles on site only in a bermed area or over a drip pan that is big enough to prevent runoff.
- ✓ If you must clean vehicles or equipment on site, clean with water only in a bermed area that will not allow rinsewater to run into gutters, streets, storm drains, or creeks.
- ✓ Do not clean vehicles or equipment on-site using soaps, solvents, degreasers, steam cleaning equipment, etc.


Earthwork & contaminated soils

- ✓ Keep excavated soil on the site where it is least likely to collect in the street. Transfer to dump trucks should take place on the site, not in the street.
- ✓ Use hay bales, silt fences, or other control measures to minimize the flow of silt off the site.
- ✓ Avoid scheduling earth moving activities during the rainy season if possible. If grading activities during wet weather are allowed in your permit, be sure to implement all control measures necessary to prevent erosion.
- ✓ Mature vegetation is the best form of erosion control. Minimize disturbance to existing vegetation whenever possible.
- ✓ If you disturb a slope during construction, prevent erosion by securing the soil with erosion control fabric, or seed with fast-growing grasses as soon as possible. Place hay bales down-slope until soil is secure.
- ✓ If you suspect contamination (from site history, discoloration, odor, texture, abandoned underground tanks or pipes, or buried debris), call your local fire department for help in determining what testing should be done.
- ✓ Manage disposal of contaminated soil according to Fire Department instructions.




Storm drain polluters may be liable for fines of up to \$10,000 per day!

Dewatering operations




- ✓ Reuse water for dust control, irrigation, or another on-site purpose to the greatest extent possible.
- ✓ Be sure to call your city's storm drain inspector before discharging water to a street, gutter, or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ✓ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the city inspector to determine what testing to do and to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.

Saw cutting



- ✓ Always completely cover or barricade storm drain inlets when saw cutting. Use filter fabric, hay bales, sand bags, or fine gravel dams to keep slurry out of the storm drain system.
- ✓ Shovel, absorb, or vacuum saw-cut slurry and pick up all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- ✓ If saw cut slurry enters a catch basin, clean it up immediately.


Paving/asphalt work



- ✓ Do not pave during wet weather or when rain is forecast.
- ✓ Always cover storm drain inlets and manholes when paving or applying seal coat, tack coat, slurry seal, or fog seal.
- ✓ Place drip pans or absorbent material under paving equipment when not in use.
- ✓ Protect gutters, ditches, and drainage courses with hay bales, sand bags, or earthen berms.
- ✓ Do not sweep or wash down excess sand from sand sealing into gutters, storm drains, or creeks. Collect sand and return it to the stockpile, or dispose of it as trash.
- ✓ Do not use water to wash down fresh asphalt concrete pavement.

from sand sealing into gutters, storm drains, or creeks. Collect sand and return it to the stockpile, or dispose of it as trash.

Concrete, grout, and mortar storage & waste disposal



- ✓ Be sure to store concrete, grout, and mortar under cover and away from drainage areas. These materials must never reach a storm drain.
- ✓ Wash out concrete equipment/trucks off-site or designate an on-site area for washing where water will flow onto dirt or into a temporary pit in a dirt area. Let the water seep into the soil and dispose of hardened concrete with trash.




Painting

- ✓ Never rinse paint brushes or materials in a gutter or street!
- ✓ Paint out excess water-based paint before rinsing brushes, rollers, or containers in a sink. If you can't use a sink, direct wash water to a dirt area and spade it in.
- ✓ Paint out excess oil-based paint before cleaning brushes in thinner.
- ✓ Filter paint thinners and solvents for reuse whenever possible. Dispose of oil-based paint sludge and unusable thinner as hazardous waste.

SURREY FARM ESTATES
LOT 3 (S-24-025)
178 TWIN OAKS DRIVE
ARCHITECTURE & SITE REVIEW

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	4185.10
CAD DWG FILE:	418510EC_LOT3.DWG
DESIGNED BY:	AV/RH
DRAWN BY:	NW
CHECKED BY:	RH
DATE:	MAY 31, 2024
SCALE:	AS SHOWN
(C) HMH	

BASMAA



REQUIRED FIRE FLOW & HYDRANTS

LOT 1: 2231 SF, TYPE VB
FIRE FLOW: 500 GPM FOR 1/2 HOUR, PER CFC APPENDIX B, TABLE B105.1(1)
HYDRANTS: 1 HYDRANT WITH AVERAGE SPACING 500' PER CFC APPENDIX C, TABLE C102.1

LOT 2 & 3: 2155 SF, TYPE VB
FIRE FLOW: 500 GPM FOR 1/2 HOUR, PER CFC APPENDIX B, TABLE B105.1(1)
HYDRANTS: 1 HYDRANT WITH AVERAGE SPACING 500' PER CFC APPENDIX C, TABLE C102.1

LOTS 4,5,6: 6827 SF, TYPE VB
FIRE FLOW: 1125 GPM FOR 1 HOUR, PER CFC APPENDIX B, TABLE B105.1(1) AND TABLE B105.1(2)
HYDRANTS: 2 HYDRANTS WITH AVERAGE SPACING 450' PER CFC APPENDIX C, TABLE C102.1

LOTS 7,8,9,10: 7699 SF, TYPE VB
FIRE FLOW: 1125 GPM FOR 1 HOUR, PER CFC APPENDIX B, TABLE B105.1(1) AND TABLE B105.1(2)
HYDRANTS: 2 HYDRANTS WITH AVERAGE SPACING 450' PER CFC APPENDIX C, TABLE C102.1

NOTES

1. PRIVATE STREETS WILL INCLUDE EMERGENCY ACCESS EASEMENTS
2. MAX HORIZONTAL LENGTH IS 200 FEET
3. CONSTRUCTION TYPE IS VB
4. OCCUPANCY GROUPS R-3
5. ACCESS ROADWAYS SHALL BE PROVIDED TO COMPLY WITH ALL OF THE FOLLOWING REQUIREMENTS:
 - a. FIRE APPARATUS ACCESS ROADWAYS SHALL HAVE A "MINIMUM" WIDTH OF A FIRE APPARATUS ACCESS ROADWAY FOR ENGINES IS 20 FEET.
 - b. FIRE ACCESS ROADWAYS SHALL HAVE A "MINIMUM" UNOBSTRUCTED VERTICAL CLEARANCE OF NOT LESS THAN 13 FEET 6 INCHES.
 - c. ALL FIRE DEPARTMENT ACCESS ROADWAYS INCLUDING THE PRIVATE STREET, DRIVEWAYS, AND EMERGENCY ACCESS EASEMENTS SHALL BE AN ALL-WEATHER SURFACE DESIGNED TO SUPPORT THE IMPOSED LOAD OF FIRE APPARATUS WITH A GROSS VEHICLE WEIGHT OF 75,000-POUNDS.
 - d. FIRE APPARATUS ACCESS ROADWAYS SHALL HAVE A "MINIMUM" INSIDE TURNING RADIUS FOR FIRE DEPARTMENT ACCESS ROADWAYS SHALL BE 30 FEET OR GREATER.
 - e. THE GRADE FOR EMERGENCY APPARATUS ACCESS ROADWAYS SHALL NOT EXCEED 10 PERCENT TO FACILITATE FIRE GROUND OPERATIONS.
 - f. TRAFFIC CALMING DEVICES ARE NOT PERMITTED ON ANY DESIGNATED FIRE ACCESS ROADWAYS UNLESS APPROVED BY THE FIRE PREVENTION & HAZARDOUS MATERIALS DIVISION.
 - g. ALL DESIGNATED FIRE LANES WITH RAISED CURBS SHALL BE PAINTED RED. "NO PARKING - FIRE LANE" SHALL BE IN WHITE PAINT, 6 INCHES IN HEIGHT WITH A MINIMUM 1 INCH STROKE. LETTERING SHALL BE PAINTED AT AN INTERVAL OF EVERY 26 FEET.
 - h. SPRINKLERS SHALL BE PROVIDED (DEFERRED SUBMITTAL)
 - i. NO COMBUSTIBLE CONSTRUCTION SHALL OCCUR PRIOR TO NEW HYDRANT INSTALLATION.

0 25 50 100
1 INCH = 50 FEET

LEGEND

PROJECT BOUNDARY	-----
EXISTING EASEMENT	-----
PROPOSED PROPERTY LINE	-----
PROPOSED EASEMENT	-----
PROPOSED BUILDING	-----
200' MAX. HOSE PULL	-----
EXISTING WATER LINE	W(E) EX 6'W W(E)
FIRE DEPARTMENT LINE (PROPOSED)	F 6'FW F
FIRE HYDRANT (E)	○
FIRE HYDRANT (P)	●
FIRE DEPARTMENT CONNECT (P)	●
PRIVATE INGRESS EGRESS EASEMENT	PIEE
EMERGENCY ACCESS EASEMENT	EAE
PUBLIC SERVICE EASEMENT	PSE
EXISTING	(E)
PROPOSED	(P)




EAST ROSS CREEK IN 36-INCH RCP

W(E)

S

SD(E)



REQUIRED FIRE FLOW & HYDRANTS

LOTS 1,11,12: 2070 SF, TYPE VB
FIRE FLOW: 1000 GPM FOR 1 HOUR, PER CFC APPENDIX B, TABLE B105.1(1)
HYDRANTS: 1 HYDRANT WITH AVERAGE SPACING 500' PER CFC APPENDIX C,
TABLE C102.1


LOTS 4,5,6: 575 SF, TYPE VB
FIRE FLOW: 1000 GPM FOR 1 HOUR, PER CFC APPENDIX B, TABLE B105.1(1) AND TABLE B105.1(2)
HYDRANTS: 2 HYDRANTS WITH AVERAGE SPACING 450' PER CFC APPENDIX C,
TABLE C102.1

LOTS 2,3,7,8,9,10: 6205 - 6830 SF, TYPE VB
FIRE FLOW: 1125 GPM FOR 1 HOUR, PER CFC APPENDIX B, TABLE B105.1(1) AND TABLE B105.1(2)
HYDRANTS: 2 HYDRANTS WITH AVERAGE SPACING 450' PER CFC APPENDIX C,
TABLE C102.1

NOTES

1. PRIVATE STREETS WILL INCLUDE EMERGENCY ACCESS EASEMENTS
2. MAX HOSE PULL LENGTH IS 200'
3. CONSTRUCTION TYPE IS V-B
4. OCCUPANCY GROUPS: R-3
5. ACCESS ROADWAYS SHALL BE PROVIDED TO COMPLY WITH ALL OF THE FOLLOWING REQUIREMENTS:
 - a. FIRE APPARATUS ACCESS ROADWAYS SHALL HAVE A "MINIMUM" WIDTH OF A FIRE APPARATUS ACCESS ROADWAY FOR ENGINES IS 20 FEET.
 - b. FIRE ACCESS ROADWAYS SHALL HAVE A "MINIMUM" UNOBSTRUCTED VERTICAL CLEARANCE OF NOT LESS THAN 13 FEET 6 INCHES.
 - c. ALL FIRE DEPARTMENT ACCESS ROADWAYS SHALL BE AN ALL-WEATHER SURFACE DESIGNED TO SUPPORT THE IMPOSED LOAD OF FIRE APPARATUS WITH A GROSS VEHICLE WEIGHT OF 75,000-POUNDS.
 - d. FIRE APPARATUS ACCESS ROADWAYS SHALL HAVE A "MINIMUM" INSIDE TURNING RADIUS FOR FIRE DEPARTMENT ACCESS ROADWAYS SHALL BE 30 FEET OR GREATER.
 - e. THE GRADE FOR EMERGENCY APPARATUS ACCESS ROADWAYS SHALL NOT EXCEED 10 PERCENT TO FACILITATE FIRE-GROUND OPERATIONS.
 - f. TRAFFIC CALMING DEVICES ARE NOT PERMITTED ON ANY DESIGNATED FIRE ACCESS ROADWAY, UNLESS APPROVED BY THE FIRE PREVENTION & HAZARDOUS MATERIALS DIVISION.
 6. ALL DESIGNATED FIRE LANES WITH RAISED CURBS SHALL BE PAINTED RED. "NO PARKING - FIRE LANE" SHALL BE IN WHITE PAINT, 6 INCHES IN HEIGHT WITH A MINIMUM 1 INCH STROKE. LETTERING SHALL BE PAINTED AT AN INTERVAL OF EVERY 25 FEET.


LEGEND



1 INCH = 30 FEET

SURREY FARM ESTATES
LOT 3 (S-24-025)
178 TWIN OAKS DRIVE
ARCHITECTURE & SITE REVIEW

10/24/2025	PER CITY COMMENTS	
9/15/2025	PER CITY COMMENTS	
7/25/2025	PER CITY COMMENTS	
4/18/2025	PER CITY COMMENTS	
3/3/2025	PER CITY COMMENTS	
NO	DATE	DESCRIPTION
PROJECT NO:		4185.10
CAD DWG FILE:		418510FA_LOT 3.DWG
DESIGNED BY:		XX
DRAWN BY:		NW
CHECKED BY:		RH
DATE:		MAY 31ST, 2024
SCALE:		AS SHOWN
(C) HMH		
<h2>FIRE ACCESS PLAN</h2>		
<p style="text-align: center;">7.1</p>		






Land Use Entitlements
Land Planning
Landscape Architecture
Civil Engineering
Utility Design
Land Surveying
Stormwater Compliance

1570 Oakland Road (408) 487-2200
San Jose, CA 95131
HMHCa.com

SURREY FARM ESTATES
LOT 3 (S-24-025)
178 TWIN OAKS DRIVE
ARCHITECTURE & SITE REVIEW


10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	4185.10
CAD DWG FILE:	418510FA.LOT3.DWG
DESIGNED BY:	RM
DRAWN BY:	NW
CHECKED BY:	RH
DATE:	MAY 31ST, 2024
SCALE:	AS SHOWN
(C) HMH	
FIRE TRUCK TURNAROUND	
7.2	

FIRE TRUCK
TURNAROUND




1 INCH = 20 FEET

PROJECT 418510FA.LOT3.DWG



1 INCH = 20 FEET



PLOTTED: 10/20/2025 2:24 PM



PLANNING APPLICATION - LOT 3 (S-24-025) ARCHITECTURAL SUBMITTAL

OUR TEAM:

Applicant: Larry Dodge

Contact: Jim Foley
223 W. Main St, Los Gatos, CA 95030
408.813.7490

Architect: PLATFORM

Architecture+Planning
Contact: Chris Hall
chris@platformmdw.com
1804 5th St
Berkeley, CA 94710
415.658.1723

Civil: HMH Engineers

Contact: Deena Morsilli
1570 Oakland Rd, San Jose, CA 95131
669.221.7817

Landscape: HMH Landscape

Contact: Shawn Taylor
1570 Oakland Rd, San Jose, CA 95131
408.487.2200

PROJECT DESCRIPTION / DATA:

Site Area: 17.55 acres
APN: 532-16-006
General Plan Landuse: AG

Proposed Project:

12 Lot Subdivision consisting of the following:
3 BMR units detached on 3 proposed lots
9 Proposed Market Rate Homes on proposed lots

Lot 3 is a proposed as market rate and part of the
12 lot subdivision. See Civil Title Pg 1.0 for detailed
Project Data.

SHEET INDEX:



G0	Title Page / Project Info
G1.0	Existing Site Photos
A1.1	Site Plan and Ground Floor Plan
A1.2	Floor Plans
A2.1	Elevations / Color & Materials
A2.2	Elevations / Color & Materials
A3.0	Building Sections
A3.1	Street Elevations / Site Sections
A4.1	Shadow Analysis


LOCATION PLAN:



VICINITY MAP:







PLATFORM

architecture / planning / research

SURREY FARMS

Los Gatos, CA


Lot 3 - Siteplan & Ground Floor Plan

PG A1.1

SB 330 Final Application Re-Submittal - **July 28th, 2025**

 Highest point of roof over natural grade
(see Section A, A3.0)

Bldg Height Information Table						
Lot #	Plan Type	Natural Grade at High Point	Proposed Grade At High point	Main Level Bldg FFE	Top of Roof (above FFE)	Bldg Height
1	D	420	422.3	423.3	24.3	27.6
2	B	424	426.9	427.9	28.6	32.5
3	B	425	433.4	434.4	28.6	38
4	A(R)	424	434.2	435.2	26	37.2
5	A	418.5	432.4	433.4	26	40.9
6	A	425.5	432.3	433.3	26	33.8
7	C	455	448.9	449.9	26.8	27.8
8	C	445	438.8	439.8	26.8	27.8
9	C	456	449	450	26.8	27.8
10	C	502	495.6	496.6	26.8	27.8
11	D	420.5	422.9	423.9	24.3	27.7
12	D	421	423	424	24.3	27.3




1" = 8' at full size (36 x 24")

Plan Type B

Plan Type B			
Floor	Cond. Area	Covered Deck/Porch	Garage
Ground Fl	2,987 sf	546 sf	653 sf
2nd Fl	2,807 sf	-	
Attic	780		
Total	6,574 sf	546sf	653 sf







Ground Floor Plan

NOTES:

1. Area of stair is counted towards 2nd Fl SF Area - not on ground floor
2. Once an attic space exceeds seven (7) feet six (6) inches in height, all areas down to five (5) feet will be counted toward the floor area ratio. (see hatched area over roofplan for qualifying attic space)
3. Roof overhangs are shown at 1'



2nd Floor Plan



3/16" = 1'-0" at full size (24 x 36")


Plan Type B

Floor	Cond. Area	Covered Deck/Porch	Garage
Ground Fl	2.987 sf	546 sf	653 sf
2nd Fl	2,807 sf	-	
Attic	780		
Total	6,574 sf	546sf	653 sf






North Elevation



South Elevation

A	Wood Siding	30 LRV Vertical Wood Siding Weathered Cedar Clear Satin	
F	Stone Veneer Accent	30 LRV Manufactured Stone Veneer El Dorado 'Sierra Cut'	
B	Painted Metal Railing	LRV 10 Architectural Grade Painted Metal	
G	Fiberglass Windows	LRV 10 Slim Profile Section	
C	Painted Trim	LRV 30 Accent Trim and Barge Boards See Body Color for Paint Finish	
H	Painted Entry Door	Varies	
D	Painted Wood Shutters	LRV 30 Exterior Straight Top Shutters. Paint to match accent trim	
I	Roll-Up Garage Door	LRV 10 Decorative Metal Roll Up Garage Door with Glass Lites	
E	Stucco	Sand Stucco Finish Painted or integral color - See Body Color Note	
J	Concrete Tile Roofs	LRV 20 Concrete Flat Tile Roof with Metal Accent Roofs.	
K	Wall Sconce 1	Rejuvenation 'Dyer' Sconce	
L	Wall Sconce 2	'Allegheny' - Outdoor Wall Sconce	
M	Wall Sconce 3	Rejuvenation 'Silas' Outdoor Wall Sconce	
1	Body Color 6	LRV 30%	
2	Body Color 5	LRV 30%	
3	Body Color 3	LRV 10%	

0 8 16 24
1" = 8' at full size (36 x 24")




NOTES:

Building Height shown on elevations for reference only and is shown as height from finished grade to top of roof, please see section pages for height per LG Municode definition

Exterior Lighting


Sec. 29.10.09015. - All permanent exterior light fixtures should utilize shields so that no bulb is visible and to ensure that light is directed to the ground surface and does not spill light onto neighboring parcels or produce glare when seen from nearby homes.



West Elevation

A Wood Siding	30 LRV Vertical Wood Siding Weathered Cedar Clear Satin	
F Stone Veneer Accent	30 LRV Manufactured Stone Veneer El Dorado 'Sierra Cut'	
B Painted Metal Railing	LRV 10 Architectural Grade Painted Metal	
G Fiberglass Windows	LRV 10 Slim Profile Section	
C Painted Trim	LRV 30 Accent Trim and Barge Boards See Body Color for Paint Finish	
H Painted Entry Door	Varies	
D Painted Wood Shutters	LRV 30 Exterior Straight Top Shutters. Paint to match accent trim	
I Roll-Up Garage Door	LRV 10 Decorative Metal Roll Up Garage Door with Glass Lites	
J Concrete Tile Roofs	LRV 20 Concrete Flat Tile Roof with Metal Accent Roofs.	
K Wall Sconce 1	Rejuvenation 'Dyer' Sconce	
L Wall Sconce 2	'Allegheny' - Outdoor Wall Sconce	
M Wall Sconce 3	Rejuvenation 'Silas' Outdoor Wall Sconce	
1 Body Color 6	LRV 30%	
2 Body Color 5	LRV 30%	
3 Body Color 3	LRV 10%	

0 8 16 24
1" = 8' at full size (36 x 24")




East Elevation



NOTES:

Building Height shown on elevations for reference only and is shown as height from finished grade to top of roof, please see section pages for height per LG Municode definition

Exterior Lighting

Sec. 29.10.09015. - All permanent exterior light fixtures should utilize shields so that no bulb is visible and to ensure that light is directed to the ground surface and does not spill light onto neighboring parcels or produce glare when seen from nearby homes.






NOTES:

Building Height is measured from the natural or finished grade, whichever is lower, to the uppermost point directly above that grade.

Exterior Lighting

Sec. 29.10.09015. - All permanent exterior light fixtures should utilize shields so that no bulb is visible and to ensure that light is directed to the ground surface and does not spill light onto neighboring parcels or produce glare when seen from nearby homes.


0 8 16 24
1" = 8' at full size (36 x 24")



A Wood Siding	30 LRV Vertical Wood Siding Weathered Cedar Clear Satin	
B Painted Metal Railing	LRV 10 Architectural Grade Painted Metal	
C Painted Trim	LRV 30 Accent Trim and Barge Boards See Body Color for Paint Finish	
D Painted Wood Shutters	LRV 30 Exterior Straight Top Shutters. Paint to match accent trim	
E Stucco	Sand Stucco Finish Painted or integral color - See Body Color Note	
F Stone Veneer Accent	30 LRV Manufactured Stone Veneer El Dorado 'Sierra Cut'	
G Fiberglass Windows	LRV 10 Slim Profile Section	
H Painted Entry Door	Varies	
I Roll-Up Garage Door	LRV 10 Decorative Metal Roll Up Garage Door with Glass Lites	
J Concrete Tile Roofs	LRV 20 Concrete Flat Tile Roof with Metal Accent Roofs.	
K Wall Sconce 1	Rejuvenation 'Dyer' Sconce	
L Wall Sconce 2	'Allegheny' - Outdoor Wall Sconce	
M Wall Sconce 3	Rejuvenation 'Silas' Outdoor Wall Sconce	
1 Body Color 6	LRV 30%	
2 Body Color 5	LRV 30%	
3 Body Color 3	LRV 10%	

1" = 8' at full size (36 x 24")






Street Elevation




Street Elevation

Bldg Height Information Table						
Lot #	Plan Type	Natural Grade at High Point	Proposed Grade At High point	Main Level Bldg FFE	Top of Roof (above FFE)	Bldg Height
1	D	420	422.3	423.3	24.3	27.6
2	B	424	426.9	427.9	28.6	32.5
3	B	425	433.4	434.4	28.6	38
4	A(R)	424	434.2	435.2	26	37.2
5	A	418.5	432.4	433.4	26	40.9
6	A	425.5	432.3	433.3	26	33.8
7	C	455	448.9	449.9	26.8	27.8
8	C	445	438.8	439.8	26.8	27.8
9	C	456	449	450	26.8	27.8
10	C	502	495.6	496.6	26.8	27.8
11	D	420.5	422.9	423.9	24.3	27.7
12	D	421	423	424	24.3	27.3







June 21st 9 AM




June 21st 12 PM




June 21st 3 PM



December 21st 9 AM



December 21st 12 PM



December 21st 3 PM

SURREY FARMS ESTATES TWIN OAKS DRIVE, LOS GATOS

DEVELOPMENT REVIEW PLAN SET LOT 3 | APP #S-24-025

NOTES:
1. SEE SHEET T-2 FOR TREE EVALUATION TABLE.
2. SEE SHEET T-3 FOR TREE APPRAISAL TABLE.
3. SEE SHEET T-4 FOR TREE PROTECTION FENCING DETAIL AND NOTES.

LEGEND

DESCRIPTION	SYMBOL
ON-SITE TREE TO REMAIN / PROTECT	●
TREE TO BE REMOVED	✗
OFF-SITE TREE TO REMAIN / PROTECT	●
TREE PROTECTION FENCING AND TPZ (SEE DETAIL ON SHEET T-4)	---



ON-SITE TREE MITIGATION TABLE

	CANOPY SIZE	QTY	REPLACEMENT REQUIREMENT	QUANTITY REQUIRED
TOTAL NUMBER OF TREES TO BE REMOVED	< 10'	3	TWO - 24" BOX	6 - 24" BOX
	11' - 25'	21	THREE - 24" BOX	63 - 24" BOX
	26' - 40'	13	FOUR - 24" BOX OR TWO - 36" BOX	26 - 36" BOX
	41' - 55'	0	SIX - 24" BOX OR THREE - 36" BOX	0 - 36" BOX
	> 55'	0	TEN - 24" BOX OR FIVE - 36" BOX	0 - 36" BOX

- IF QUANTITY OF PROPOSED TREES ARE NOT EQUAL TO OR GREATER THAN REQUIRED TREES, THE PROJECT IS SUBJECT TO MITIGATION FEES PER CITY OF LOS GATOS POLICY.
- SEE ARBORIST REPORT, DATED DECEMBER 15, 2024, REVISED JULY 23, 2025 FOR ADDITIONAL INFORMATION.

TREE MITIGATION SUMMARY TABLE

	QUANTITY	SIZE
TOTAL TREES REQUIRED TO MEET MITIGATION REQUIREMENTS ON-SITE	69	24" BOX
26	36" BOX	
TOTAL PROPOSED TREES ON-SITE (NOT INCLUDING STREET TREES)	2	24" BOX
0	36" BOX	
REMAINING NUMBER OF TREES NOT BEING MITIGATED FOR	67	24" BOX
26	36" BOX	


NOTES:

1. TREE REMOVAL SHALL BE BY CONTRACTOR.
2. SEE TREE EVALUATION SUMMARY FOR INFORMATION INCLUDING SPECIES AND DIAMETER.
3. CONTRACTOR TO VERIFY ACTUAL CANOPY CLEARANCES WITHIN 100' OF EVERY HOME. UNDER ARBORIST SUPERVISION, PRUNE AND TRIM TREES WITHIN ACCORDANCE ON TREE SPACING DIAGRAM ON SHEET 10.1.

EXISTING TREES TO REMAIN AND PROTECT

EXISTING ON-SITE TREES TO REMAIN / PROTECT	4

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
1/8/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	4185.10
CAD DWG FILE:	418510CL - LOT 3.DWG
DESIGNED BY:	JN
DRAWN BY:	JN
CHECKED BY:	ST
DATE:	JUNE 6, 2025
SCALE:	1"=20'
© HMH	



TREE EVALUATION NOTES:
*SEE SHEET T-4 FOR TREE PROTECTION REQUIREMENT DETAILS

**REASON FOR REMOVAL

1. THE TREE IS DEAD, SEVERELY DISEASED, DECAYED OR DISFIGURED TO SUCH AN EXTENT THAT THE TREE IS UNABLE TO RECOVER OR RETURN TO A HEALTHY AND STRUCTURALLY SOUND CONDITION.
2. THE TREE HAS A TREE RISK RATING OF EXTREME OR HIGH ON THE ISA TREE RISK RATING MATRIX AS SET FORTH IN THE ISA TREE RISK ASSESSMENT BEST MANAGEMENT PRACTICES, OR SUCCESSOR PUBLICATION.
3. THE TREE IS CROWDING OTHER PROTECTED TREES TO THE EXTENT THAT REMOVAL OR SEVERE PRUNING IS NECESSARY TO ENSURE THE LONG-TERM VIABILITY OF ADJACENT AND MORE SIGNIFICANT TREES.
4. THE RETENTION OF THE TREE RESTRICTS THE ECONOMIC ENJOYMENT OF THE PROPERTY OR CREATES AN UNUSUAL HARDSHIP FOR THE PROPERTY OWNER BY SEVERELY LIMITING THE USE OF THE PROPERTY IN A MANNER NOT TYPICALLY EXPERIENCED BY OWNERS OF SIMILARLY SITUATED PROPERTIES, AND THE APPLICANT HAS DEMONSTRATED TO THE SATISFACTION OF THE DIRECTOR OR DECIDING BODY THAT THERE ARE NO REASONABLE ALTERNATIVES TO PRESERVE THE TREE.

LOT 3
TREE EVALUATION TABLE

Tree-ID	Existing Tree	Tag Number	SPP	Rate To protected	DBH_IN	CIRC_IN	HEIGHT_FT	N/S_FT	E/W_FT	SPREAD Const Impact	SPREAD Const Impact	NOTE	Species Rate To protected	LARGE PROTECTED	HEALTH PROTECTED	STRUCTURE Rating	OVRL Rating	COND Const Impact	Tolerance Rate To Const Impact	COND OVRL w construction Numeronym	TPZ_FT_R Const Impact	TPZ_FT_R Radius	COND OVRL w Const Impact	MOC	Min Offset_IN	Min Depth_IN	RETENTION Rating	INSPECT_ Inspect_	SAVE, REMOVE, OFF-SITE	REASON FOR REMOVAL**	TREE PROTECTION REQUIREMENT*
535	319	Quercus agrifolia			8	25.13274123	28	15	12					X	4	3	3.5	No	G	5	4.25	4	10	HDD	8	#N/A	HIGH	SAVE	Type 1		
536	320	Olea europaea			5	15.7096327	31	18	13					X	4	4	4	No	M	3	3.5	2.5	6.25	HDD	5	#N/A	HIGH	REMOVE	4		
537		Olea europaea			4	12.56637061	16	18	16					X	4	2	3	No	M	3	3	2	5	HDD	4	#N/A	MODERATE	REMOVE	4		
538	321	Olea europaea			4	12.56637061	36	20	18					X	4	4	4	No	M	3	3.5	2	5	HDD	4	#N/A	HIGH	REMOVE	4		
539		Quercus agrifolia			4	12.56637061	15	10	10					X	3	3	3	No	G	5	4	2	5	HDD	4	#N/A	HIGH	SAVE	Type 1		
540	322	Quercus lobata	X		13	40.8407045	35	26	28	Poor Tree Structure				X	3	3	3	No	M	3	3	6.5	16.25	HDD	13	#N/A	MODERATE	REMOVE	1		
541		Quercus lobata	X		17	53.40707511	50	33	27	Dead Wood				X	3	3	3	No	M	3	3	8.5	21.25	HDD	17	#N/A	MODERATE	REMOVE	1		
543	329	Quercus lobata			4	12.56637061	24	1	1	Severe Decline				X	2	1	1.5	No	M	3	2.25	2	5	HDD	4	#N/A	LOW	REMOVE	1		
544	330	Quercus agrifolia			7	21.99114858	32	8	6					X	4	4	4	No	G	5	4.5	3.5	8.75	HDD	7	#N/A	HIGH	REMOVE	4		
545		Quercus lobata	X		13	40.8407045	34	1	2	Severe Decline				X	2	1	1.5	No	M	3	2.25	6.5	16.25	HDD	13	#N/A	LOW	REMOVE	1		
546	334	Quercus agrifolia			8	25.13274123	28	12	10					X	4	4	4	No	G	5	4.5	4	10	HDD	8	#N/A	HIGH	REMOVE	4		
547	333	Quercus agrifolia	X		15	47.1238898	42	23	20					X	4	4	4	No	G	5	4.5	7.5	18.75	HDD	15	#N/A	HIGH	REMOVE	4		
548		Quercus lobata	X		11	34.55751919	38	12	8	Severe Decline				X	2	2	2	No	M	3	2.5	5.5	13.75	HDD	11	#N/A	LOW	REMOVE	1		
549		Quercus lobata	X		15	47.1238898	36	20	20	Dead Wood				X	2	3	2.5	No	M	3	2.75	7.5	18.75	HDD	15	#N/A	MODERATE	REMOVE	1		
550	301	Quercus agrifolia			9	28.27433388	22	20	20	Crowded Growing Conditions				X	4	4	4	No	G	5	4.5	4.5	11.25	HDD	9	#N/A	HIGH	REMOVE	3		
551	343	Quercus lobata	X		17	53.40707511	40	34	30	Severe Decline				X	3	3	3	No	M	3	3	8.5	21.25	HDD	17	#N/A	MODERATE	REMOVE	1		
552		Olea europaea			4	12.56637061	17	18	23					X	4	3	3.5	No	M	3	3.25	2	5	HDD	4	#N/A	MODERATE	REMOVE	4		
553	344	Quercus agrifolia	X		12	37.69911184	28	16	15					X	4	4	4	No	G	5	4.5	6	15	HDD	12	#N/A	HIGH	REMOVE	4		
554	609	Quercus agrifolia			8	25.13274123	25	13	11					X	4	4	4	No	G	5	4.5	4	10	HDD	8	#N/A	HIGH	REMOVE	4		
555	345	Quercus agrifolia			9	28.27433388	31	20	18					X	4	4	4	No	G	5	4.5	4.5	11.25	HDD	9	#N/A	HIGH	REMOVE	4		
556	346	Quercus lobata	X		15	47.1238898	42	25	25	Dead Limbs				X	3	3	3	No	M	3	3	7.5	18.75	HDD	15	#N/A	MODERATE	REMOVE	1		
557	347	Quercus lobata	X		18	56.5486776	30	28	31	Dead Limbs				X	4	3	3.5	No	M	3	3.25	9	22.5	HDD	18	#N/A	MODERATE	REMOVE	1		
558	348	Quercus lobata	X		13	40.8407045	27	24	22	Dead Limbs				X	4	3	3.5	No	M	3	3.25	6.5	16.25	HDD	13	#N/A	MODERATE	REMOVE	1		
559		Quercus lobata			9	28.27433388	34	12	6	Severe Decline				X	3	3	3	No	M	3	3	4.5	11.25	HDD	9	#N/A	MODERATE	REMOVE	1		
560		Quercus lobata	X		16	50.26548246	41	27	18					X	4	3	3.5	No	M	3	3.25	8	20	HDD	16	#N/A	MODERATE	REMOVE	4		
561		Olea europaea			8	25.13274123	26	23	20	Severe Decline				X	2	2	2	No	M	3	2.5	4	10	HDD	8	#N/A	LOW	REMOVE	1		
562		Quercus lobata	X		26	81.68140899	48	35	40	Dead Wood				X	4	4	4	No	M	3	3.5	13	32.5	HDD	26	#N/A	HIGH	REMOVE	1		
563	338	Quercus agrifolia			9	28.27433388	30	28	22																						

LOT 3

TREE APPRAISAL TABLE
REPRODUCTION METHOD - TRUNK FORMULA TECHNIQUE

TREE #	BOTANICAL NAME	COMMON NAME	DBH (IN)	SUBJECT TREE							REPLACEMENT TREE				CALCULATIONS			TOTAL	SAVE, REMOVE, OFF-SITE	
				CROSS-SECTIONAL AREA = $(DBH^2)*0.7854$	HEALTH %	STRUCTURE %	FORM %	CONDITION %	FUNCTIONAL LIMITATIONS %	EXTERNAL LIMITATIONS %	LCANT	(RTD) REPLACEMENT TREE DIAMETER (IN)	CROSS-SECTIONAL AREA = $(RTD^2)*0.7854$	REPLACEMENT TREE COST	UNIT TREE COST	BASIC REPRODUCTION COST	DEPRECIATED REPRODUCTION COST			
535	Quercus agrifolia	Coast Live Oak	8.0	50.27	70	50	70	63%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,329.64	\$ 842	\$ 600.00	\$ 1,400	SAVE
536	Olea europaea	Olive	5.0	19.64	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 519.39	\$ 364	\$ 600.00	\$ 1,000	REMOVE
537	Olea europaea	Olive	4.0	12.57	70	30	70	57%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 332.41	\$ 188	\$ 600.00	\$ 800	REMOVE
538	Olea europaea	Olive	4.0	12.57	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 332.41	\$ 233	\$ 600.00	\$ 800	REMOVE
539	Quercus agrifolia	Coast Live Oak	4.0	12.57	50	50	70	57%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 332.41	\$ 188	\$ 600.00	\$ 800	REMOVE
540	Quercus lobata	Valley Oak	13.0	132.73	50	50	50	50%	80%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 3,511.08	\$ 1,404	\$ 600.00	\$ 2,000	REMOVE
541	Quercus lobata	Valley Oak	17.0	226.98	50	50	50	50%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 6,004.16	\$ 3,002	\$ 600.00	\$ 3,600	REMOVE
542	Quercus agrifolia	Coast Live Oak	7.0	38.48	50	30	70	50%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,018.01	\$ 509	\$ 600.00	\$ 1,100	REMOVE
543	Quercus lobata	Valley Oak	4.0	12.57	30	10	30	23%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 332.41	\$ 78	\$ 600.00	\$ 700	REMOVE
544	Quercus agrifolia	Coast Live Oak	7.0	38.48	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,018.01	\$ 713	\$ 600.00	\$ 1,300	REMOVE
545	Quercus lobata	Valley Oak	13.0	132.73	30	10	30	23%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 3,511.08	\$ 819	\$ 600.00	\$ 1,400	REMOVE
546	Quercus agrifolia	Coast Live Oak	8.0	50.27	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,329.64	\$ 931	\$ 600.00	\$ 1,500	REMOVE
547	Quercus agrifolia	Coast Live Oak	15.0	176.72	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 4,674.52	\$ 3,272	\$ 600.00	\$ 3,900	REMOVE
548	Quercus lobata	Valley Oak	11.0	95.03	30	30	30	30%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 2,513.85	\$ 754	\$ 600.00	\$ 1,400	REMOVE
549	Quercus lobata	Valley Oak	15.0	176.72	30	50	50	43%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 4,674.52	\$ 2,026	\$ 600.00	\$ 2,600	REMOVE
550	Quercus agrifolia	Coast Live Oak	9.0	63.62	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,682.83	\$ 1,178	\$ 600.00	\$ 1,800	REMOVE
551	Quercus lobata	Valley Oak	17.0	226.98	50	50	50	50%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 6,004.16	\$ 3,002	\$ 600.00	\$ 3,600	REMOVE
552	Olea europaea	Olive	4.0	12.57	70	50	70	63%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 332.41	\$ 211	\$ 600.00	\$ 800	REMOVE
553	Quercus agrifolia	Coast Live Oak	12.0	113.10	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 2,991.69	\$ 2,094	\$ 600.00	\$ 2,700	REMOVE
554	Quercus agrifolia	Coast Live Oak	8.0	50.27	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,329.64	\$ 931	\$ 600.00	\$ 1,500	REMOVE
555	Quercus agrifolia	Coast Live Oak	9.0	63.62	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,682.83	\$ 1,178	\$ 600.00	\$ 1,800	REMOVE
556	Quercus lobata	Valley Oak	15.0	176.72	50	50	50	50%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 4,674.52	\$ 2,337	\$ 600.00	\$ 2,900	REMOVE
557	Quercus lobata	Valley Oak	18.0	254.47	70	50	70	63%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 6,731.30	\$ 4,263	\$ 600.00	\$ 4,900	REMOVE
558	Quercus lobata	Valley Oak	13.0	132.73	70	50	70	63%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 3,511.08	\$ 2,224	\$ 600.00	\$ 2,800	REMOVE
559	Quercus lobata	Valley Oak	9.0	63.62	50	50	50	50%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,682.83	\$ 841	\$ 600.00	\$ 1,400	REMOVE
560	Quercus lobata	Valley Oak	16.0	201.06	70	50	70	63%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 5,318.56	\$ 3,368	\$ 600.00	\$ 4,000	REMOVE
561	Olea europaea	Olive	8.0	50.27	30	30	30	30%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,329.64	\$ 399	\$ 600.00	\$ 1,000	REMOVE
562	Quercus lobata	Valley Oak	26.0	530.93	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 14,044.32	\$ 9,831	\$ 600.00	\$ 10,400	REMOVE
563	Quercus agrifolia	Coast Live Oak	9.0	63.62	70	70	70	70%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 1,682.83	\$ 1,178	\$ 600.00	\$ 1,800	REMOVE
564	Quercus lobata	Valley Oak	28.0	615.75	50	70	70	63%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 16,288.09	\$ 10,316	\$ 600.00	\$ 10,900	REMOVE
565	Quercus lobata	Valley Oak	17.0	226.98	70	50	50	57%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 6,004.16	\$ 3,402	\$ 600.00	\$ 4,000	REMOVE
566	Quercus agrifolia	Coast Live Oak	36.0	1017.88	90	70	80	80%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 26,925.21	\$ 21,540	\$ 600.00	\$ 22,100	SAVE
567	Quercus lobata	Valley Oak	19.0	283.53	70	50	70	63%	100%	100%	24" Box	3.8	11.34	\$ 300.00	\$ 26.45	\$ 7,500.00	\$ 4,750	\$ 600.00	\$ 5,400	REMOVE
568	Quercus lobata	Valley Oak	22.0	380.13	50	7														

TREE PROTECTION NOTES

SITE PREPARATION:
ALL EXISTING TREES SHALL BE FENCED WITHIN OR AT THE DRIP LINE (FOLIAR SPREAD) OF THE TREE. DEPENDING ON THE LOCATION OF THE TREE THE FENCING MAY NOT BE ABLE TO BE AT THE DRIPLINE. EXAMPLES OF THIS WOULD BE PUBLIC RIGHT OF WAY, NEAR PROPERTY LINES OR AROUND EXISTING STRUCTURES TO REMAIN. WHERE COMPLETE DRIP LINE FENCING IS NOT POSSIBLE, THE ADDITION OF STRAW WADDLES AND ORANGE SNOW FENCING WRAPPING THE TRUNK SHALL BE INSTALLED PER THE TREE PROTECTION DETAIL. THE FENCE SHOULD BE A MINIMUM OF SIX FEET HIGH, MADE OF GALVANIZED 11-GAUGE WIRE MESH WITH GALVANIZED POSTS OR ANY MATERIAL SUPERIOR IN QUALITY. A TREE PROTECTION ZONE (TPZ) SIGN SHALL BE AFFIXED TO FENCING AT APPROPRIATE INTERVALS AS DETERMINED BY THE ARBORIST ON SITE. SEE TREE PROTECTION DETAIL FOR ADDITIONAL INFORMATION, INCLUDING TREE PROTECTION ZONE SIGN. IF THE FENCE IS WITHIN THE DRIP LINE OF THE TREES, THE FOLIAR FRINGE SHALL BE RAISED TO OFFSET THE CHANCE OF LIMB DAMAGE FROM ACTIVE CONSTRUCTION.

ACTIVE CONSTRUCTION:
ALL CONTRACTORS, SUBCONTRACTORS AND OTHER PERSONNEL SHALL BE WARNED THAT ENCROACHMENT WITHIN THE FENCED AREA AND DRIPLINE IS PROHIBITED WITHOUT THE CONSENT OF THE CERTIFIED ARBORIST ON THE JOB. THIS INCLUDES, BUT IS NOT LIMITED TO, STORAGE OF LUMBER AND OTHER MATERIALS, DISPOSAL OF PAINTS, SOLVENTS OR OTHER NOXIOUS MATERIALS, PARKED CARS, GRADING EQUIPMENT OR OTHER HEAVY EQUIPMENT. IF CONSTRUCTION ACTIVITY NEEDS TO HAPPEN IN THE TPZ THE FENCE CAN BE MOVED TEMPORARILY FOR DELIVERY OF CONSTRUCTION MATERIALS. THE CONTRACTOR SHOULD MAKE ACCOMMODATIONS TO OFF LOAD ITEMS SUCH AS TRUSSES, TIMBER, PLASTERBOARD, WALLBOARD, CONCRETE, GYPSUM BOARD, FLOORING, ROOFING OR ANY OTHER HEAVY CONSTRUCTION MATERIAL OUTSIDE THE FOLIAR SPREAD OF THE TREE SO THERE IS NO HEAVY EQUIPMENT NEEDED THAT COULD CAUSE DAMAGE TO THE CANOPY OF THE TREE OR COMPACT THE ROOT ZONE. THE TREE PROTECTION FENCING SHOULD BE REESTABLISHED PER THE PLANS AND DETAILS IMMEDIATELY AFTER ANY ACTIVITY THROUGH THE TPZ. PENALTIES, BASED ON THE COST OF REMEDIAL REPAIRS AND THE EVALUATION GUIDE PUBLISHED BY THE INTERNATIONAL SOCIETY OF ARBORICULTURE, SHALL BE ASSESSED FOR DAMAGES TO THE TREES.

GRADING/EXCAVATING:
ALL GRADING PLANS THAT SPECIFY GRADING WITHIN THE DRIP LINE OF ANY TREE, OR WITHIN THE DISTANCE FROM THE TRUNK AS OUTLINED IN THE SITE PREPARATION SECTION ABOVE WHEN SAID DISTANCE IS OUTSIDE THE DRIP LINE, SHALL FIRST BE REVIEWED BY A CERTIFIED ARBORIST. PROVISIONS FOR AERATION, DRAINAGE, PRUNING, TUNNELING BEHIND ROOTS, ROOT PRUNING OR OTHER NECESSARY ACTIONS TO PROTECT THE TREES SHALL BE OUTLINED BY AN ARBORIST. IF TRENCHING IS NECESSARY WITHIN THE AREA AS DESCRIBED ABOVE, SAID TRENCHING SHALL BE UNDERTAKEN BY HAND LABOR AND DUG DIRECTLY BEHIND THE TRUNK OF THE TREE. ALL ROOTS 2 INCHES OR LARGER SHALL BE TUNNELED UNDER AND OTHER ROOTS SHALL BE CUT SMOOTHLY TO THE TRUNK SIDE OF THE TRENCH. THE TRUNK SIDE SHOULD BE DRAINED IMMEDIATELY WITH TWO LAYERS OF UNTREATED BURLAP TO A DEPTH OF 3 FEET FROM THE SURFACE. THE BURLAP SHALL BE SOAKED NIGHTLY AND LEFT IN PLACE UNTIL THE TRENCH IS BACK FILLED TO THE ORIGINAL LEVEL. AN ARBORIST SHALL EXAMINE THE TRENCH PRIOR TO BACK FILLING TO ASCERTAIN THE NUMBER AND SIZE OF ROOTS CUT, SO AS TO SUGGEST THE NECESSARY REMEDIAL REPAIRS.

REMEDIAL REPAIRS:
AN ARBORIST SHALL HAVE THE RESPONSIBILITY OF OBSERVING ALL ONGOING ACTIVITIES THAT MAY AFFECT THE TREES AND PRESCRIBING NECESSARY REMEDIAL WORK TO ENSURE THE HEALTH AND STABILITY OF THE TREES. THIS INCLUDES, BUT IS NOT LIMITED TO, ALL ARBORIST ACTIVITIES BROUGHT OUT IN THE PREVIOUS SECTIONS. IN ADDITION, PRUNING, AS OUTLINED IN INTERNATIONAL SOCIETY OF ARBORICULTURE BEST MANAGEMENT PRACTICES: PRUNING AND ANSI A300 PART 1 STANDARD PRACTICES: PRUNING, SHALL BE PRESCRIBED AS NECESSARY. FERTILIZING, AERATION, IRRIGATION, PEST CONTROL AND OTHER ACTIVITIES SHALL BE PRESCRIBED ACCORDING TO THE TREE NEEDS, LOCAL SITE REQUIREMENTS, AND STATE AGRICULTURAL PEST CONTROL LAWS. ALL SPECIFICATIONS SHALL BE IN WRITING. FOR PEST CONTROL OPERATIONS, CONSULT THE LOCAL COUNTY AGRICULTURAL COMMISSIONER'S OFFICE FOR INDIVIDUALS LICENSED AS PEST CONTROL ADVISORS OR PEST CONTROL OPERATORS.

FINAL INSPECTION:
UPON COMPLETION OF THE PROJECT, THE ARBORIST SHALL REVIEW ALL WORK UNDERTAKEN THAT MAY IMPACT THE EXISTING TREES. SPECIAL ATTENTION SHALL BE GIVEN TO CUTS AND FILLS, COMPACTING, DRAINAGE, PRUNING AND FUTURE REMEDIAL WORK. AN ARBORIST SHOULD SUBMIT A FINAL REPORT IN WRITING OUTLINING THE ONGOING REMEDIAL CARE FOLLOWING THE FINAL INSPECTION.

TREE REMOVAL NOTES

- CONSTRUCTION PROTECTION FOR TREES MUST BE PROVIDED BEFORE GRADING OR OTHER EQUIPMENT IS ALLOWED ON THE PROPERTY. SEE DETAILS AND NOTES ON THIS SHEET.
- ALL TREES SHOWN FOR REMOVAL ARE PERMITTED UNDER CITY PD PERMIT. A NESTING BIRD SURVEY MAY BE REQUIRED IF TREE REMOVAL IS TO TAKE PLACE BETWEEN FEBRUARY 1 AND AUGUST 31. A QUALIFIED BIOLOGIST MUST COMPLETE THIS REPORT PRIOR TO TREE REMOVAL DONE DURING THE NESTING SEASON. REFER TO CONDITIONS OF THE PERMIT FOR ADDITIONAL INFORMATION.
- CONTRACTOR SHALL TAKE CARE WHEN REMOVING TREES ADJACENT TO TREES TO REMAIN. PROVISIONS FOR THE PROTECTION OF EXISTING TREES MUST BE TAKEN INCLUDING WRAPPING THE TRUNK OF THE ADJACENT TREE PER THE TREE PROTECTION DETAIL. WHEN REMOVING ROOTS, CARE MUST BE TAKEN NOT TO DAMAGE ROOTS OF TREE TO REMAIN. ROOT PRUNING MAY BE NECESSARY AND MUST BE DONE UNDER THE SUPERVISION OF THE ARBORIST.
- THE CONTRACTOR SHALL VISIT THE PROJECT SITE PRIOR TO BIDDING TO DETERMINE THE EXACT EXTENT OF ALL SITE DEMOLITION ITEMS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF ALL EXISTING UTILITIES IN THE FIELD PRIOR TO CONSTRUCTION. LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE AND ARE FOR GENERAL INFORMATION ONLY. HE SHALL BE RESPONSIBLE FOR MAKING HIMSELF FAMILIAR WITH ALL UNDERGROUND CONDITIONS PRIOR TO COMMENCEMENT OF WORK.
- THESE PLANS MAY NOT SHOW ALL EXISTING CITY ELECTRICAL FACILITIES INCLUDING, BUT NOT LIMITED TO, TRAFFIC SIGNALS, STREETLIGHT AND TRAFFIC SIGNAL COMMUNICATION EQUIPMENT, CONDUIT, PULL BOXES, AND WIRING.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL SUCH FACILITIES AND FOR REPAIRING ANY SUCH FACILITIES THAT ARE DAMAGED DURING CONSTRUCTION. PAYMENT FOR LOCATING, COORDINATING, AND REPAIRING EXISTING CITY ELECTRICAL FACILITIES WILL BE DEEMED INCLUDED IN OTHER ITEMS OF WORK, AND NO ADDITIONAL COMPENSATION SHALL BE MADE THEREOF. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE SPECIFICATIONS & DETAILS.
- THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT (U.S.A.) AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION ON THIS PROJECT. CALL U.S.A. AT (800) 624-2444
- THE CONTRACTOR SHALL BE RESPONSIBLE UNDER THIS CONTRACT FOR REPAIRING AND REPLACING, AT HIS OWN EXPENSE, ANY STRUCTURES, FENCES, WALLS, OR PLANT LIFE DAMAGED OR DESTROYED BY HIS OPERATION. LIKEWISE, HE SHALL BE RESPONSIBLE FOR REPAIRING OR REPLACING ANY AND ALL DAMAGES, OCCURRING BY HIS OPERATION, ON ADJACENT PROPERTIES AND ANYWHERE OUTSIDE THE CONTRACT LIMIT LINES. THE DAMAGED ITEMS SHALL BE RESTORED TO THEIR ORIGINAL CONDITIONS AND TO THE SATISFACTION OF THE PROJECT SUPERINTENDENT.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO KEEP ALL STREET RIGHT-OF-WAYS CLEAN TO THE SATISFACTION OF THE PROJECT SUPERINTENDENT ALL ITEMS INDICATED TO BE REMOVED SHALL BE DISPOSED OF FROM THE PROJECT SITE, EXCEPT ITEMS INDICATED TO BE RE-INSTALLED.
- ALL TREES TO BE REMOVED SHALL HAVE THEIR STUMPS GROUND DOWN TO A MINIMUM DEPTH OF 24" REMOVE ALL LARGE ROOTS FROM PLANTING AREAS A MINIMUM DISTANCE OF 5' BEYOND THE DRIP LINE OF THE TREE.

SEC. 29.10.1005. PROTECTION OF TREES DURING CONSTRUCTION

(A) PROTECTIVE TREE FENCING SHALL SPECIFY THE FOLLOWING:

- SIZE AND MATERIALS. SIX (6) FOOT HIGH CHAIN LINK FENCING, MOUNTED ON TWO-INCH DIAMETER GALVANIZED IRON POSTS, SHALL BE DRIVEN INTO THE GROUND TO A DEPTH OF AT LEAST TWO (2) FEET AT NO MORE THAN 10-FOOT SPACING. FOR PAVING AREA THAT WILL NOT BE DEMOLISHED AND WHEN STIPULATED IN A TREE PRESERVATION PLAN, POSTS MAY BE SUPPORTED BY A CONCRETE BASE.
- AREA TYPE TO BE FENCED.
 - TYPE I: ENCLOSURE WITH CHAIN LINK FENCING OF EITHER THE ENTIRE DRIPLINE AREA OR AT THE TREE PROTECTION ZONE (TPZ), WHEN SPECIFIED BY A CERTIFIED OR CONSULTING ARBORIST.
 - TYPE II: ENCLOSURE FOR STREET TREES LOCATED IN A PLANTER STRIP: CHAIN LINK FENCE AROUND THE ENTIRE PLANTER STRIP TO THE OUTER BRANCHES.
 - TYPE III: PROTECTION FOR A TREE LOCATED IN A SMALL PLANTER CUTOUT ONLY (SUCH AS DOWNTOWN): ORANGE PLASTIC FENCING SHALL BE WRAPPED AROUND THE TRUNK FROM THE GROUND TO THE FIRST BRANCH WITH 2-INCH WOODEN BOARDS BOUND SECURELY ON THE OUTSIDE. CAUTION SHALL BE USED TO AVOID DAMAGING ANY BARK OR BRANCHES.
- DURATION OF TYPE I, II, III FENCING. FENCING SHALL BE ERECTED BEFORE DEMOLITION, GRADING OR CONSTRUCTION PERMITS ARE ISSUED AND REMAIN IN PLACE UNTIL THE WORK IS COMPLETED. CONTRACTOR SHALL FIRST OBTAIN THE APPROVAL OF THE PROJECT ARBORIST ON RECORD PRIOR TO REMOVING A TREE PROTECTION FENCE.
- WARNING SIGN. EACH TREE FENCE SHALL HAVE PROMINENTLY DISPLAYED AN 8.5 X 11-INCH SIGN STATING: "WARNING—TREE PROTECTION ZONE—THIS FENCE SHALL NOT BE REMOVED AND IS SUBJECT TO PENALTY ACCORDING TO TOWN CODE 29.10.1025".
- ALL PERSONS SHALL COMPLY WITH THE FOLLOWING PRECAUTIONS.
 - PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, INSTALL THE FENCE AT THE DRIPLINE, OR TREE PROTECTION ZONE (TPZ) WHEN SPECIFIED IN AN APPROVED ARBORIST REPORT, AROUND ANY TREE AND/OR VEGETATION TO BE RETAINED WHICH COULD BE AFFECTED BY THE CONSTRUCTION AND PROHIBIT ANY STORAGE OF CONSTRUCTION MATERIALS OR OTHER MATERIALS, EQUIPMENT CLEANING, OR PARKING OF VEHICLES WITHIN THE TPZ. THE DRIPLINE SHALL NOT BE ALTERED IN ANY WAY SO AS TO INCREASE THE ENCROACHMENT OF THE CONSTRUCTION.
 - PROHIBIT ALL CONSTRUCTION ACTIVITIES WITHIN THE TPZ, INCLUDING BUT NOT LIMITED TO: EXCAVATION, GRADING, DRAINAGE AND LEVELING WITHIN THE DRIPLINE OF THE TREE UNLESS APPROVED BY THE DIRECTOR.
 - PROHIBIT DISPOSAL OR DEPOSITING OF OIL, GASOLINE, CHEMICALS OR OTHER HARMFUL MATERIALS WITHIN THE DRIPLINE OR IN DRAINAGE CHANNELS, SWALES OR AREAS THAT MAY LEAD TO THE DRIPLINE OF A PROTECTED TREE.
 - PROHIBIT THE ATTACHMENT OF WIRES, SIGNS OR ROPES TO ANY PROTECTED TREE.
 - DESIGN UTILITY SERVICES AND IRRIGATION LINES TO BE LOCATED OUTSIDE OF THE DRIPLINE WHEN FEASIBLE.
 - RETAIN THE SERVICES OF A CERTIFIED OR CONSULTING ARBORIST WHO SHALL SERVE AS THE PROJECT ARBORIST FOR PERIODIC MONITORING OF THE PROJECT SITE AND THE HEALTH OF THOSE TREES TO BE PRESERVED. THE PROJECT ARBORIST SHALL BE PRESENT WHENEVER ACTIVITIES OCCUR WHICH MAY POSE A POTENTIAL THREAT TO THE HEALTH OF THE TREES TO BE PRESERVED AND SHALL DOCUMENT ALL SITE VISITS.
 - THE DIRECTOR AND PROJECT ARBORIST SHALL BE NOTIFIED OF ANY DAMAGE THAT OCCURS TO A PROTECTED TREE DURING CONSTRUCTION SO THAT PROPER TREATMENT MAY BE ADMINISTERED. (ORD. NO. 2114, §§ I, II, 8-4-03)

SEC. 29.10.1010. PRUNING AND MAINTENANCE

ALL PRUNING SHALL BE IN ACCORDANCE WITH THE CURRENT VERSION OF THE INTERNATIONAL SOCIETY OF ARBORICULTURE BEST MANAGEMENT PRACTICES—TREE PRUNING AND ANSI A300-PART 1 TREE, SHRUB AND OTHER WOODY PLANT MANAGEMENT—STANDARD PRACTICES, (PRUNING) AND ANY SPECIAL CONDITIONS AS DETERMINED BY THE DIRECTOR. FOR DEVELOPMENTS, WHICH REQUIRE A TREE PRESERVATION REPORT, A CERTIFIED OR CONSULTING ARBORIST SHALL BE IN REASONABLE CHARGE OF ALL ACTIVITIES INVOLVING PROTECTED TREES, INCLUDING PRUNING, CABLEING AND ANY OTHER WORK IF SPECIFIED.

- ANY PUBLIC UTILITY INSTALLING OR MAINTAINING ANY OVERHEAD WIRES OR UNDERGROUND PIPES OR CONDUITS IN THE VICINITY OF A PROTECTED TREE SHALL OBTAIN PERMISSION FROM THE DIRECTOR BEFORE PERFORMING ANY WORK, INCLUDING PRUNING, WHICH MAY CAUSE INJURY TO A PROTECTED TREE. (E.G. CABLE TV/FIBER OPTIC TRENCHING, GAS, WATER, SEWER TRENCH, ETC.).
- PRUNING FOR CLEARANCE OF UTILITY LINES AND ENERGIZED CONDUCTORS SHALL BE PERFORMED IN COMPLIANCE WITH THE CURRENT VERSION OF THE AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI) A300 (PART 1)-PRUNING, SECTION 5.9 UTILITY PRUNING. USING SPIKES OR GAFFS WHEN PRUNING, EXCEPT WHERE NO OTHER ALTERNATIVE IS AVAILABLE, IS PROHIBITED.
- NO PERSON SHALL PRUNE, TRIM, CUT OFF, OR PERFORM ANY WORK, ON A SINGLE OCCASION OR CUMULATIVELY, OVER A THREE-YEAR PERIOD, AFFECTING TWENTY-FIVE PERCENT OR MORE OF THE CROWN OF ANY PROTECTED TREE WITHOUT FIRST OBTAINING A PERMIT PURSUANT TO THIS DIVISION EXCEPT FOR POLLARDING OF FRUITLESS MULBERRY TREES (*MORUS ALBA*) OR OTHER SPECIES APPROVED BY THE TOWN ARBORIST. APPLICATIONS FOR A PRUNING PERMIT SHALL INCLUDE PHOTOGRAPHS INDICATING WHERE PRUNING IS PROPOSED.
- NO PERSON SHALL REMOVE ANY HERITAGE TREE OR LARGE PROTECTED TREE BRANCH OR ROOT THROUGH PRUNING OR OTHER METHOD GREATER THAN FOUR (4) INCHES IN DIAMETER (12.5" IN CIRCUMFERENCE) WITHOUT FIRST OBTAINING A PERMIT PURSUANT TO THIS DIVISION.

Tree Protection Zone (TPZ) shown in gray (radius of TPZ equals 10-times the diameter of the tree or 10-feet, whichever is greater).

Type I Tree Protection: Layout configuration applies to all Protected Trees, matching the site diagram with the tree preservation report (TPR) distances written for this project. Fencing should be shown on plans as it will be installed. A curved fence for a TPZ is generally not practical.

Inspection pass/fail is dependent on correct layout and mounted sign placard.

Place two (2) 8.5" x 11" covered warning signs at each tree.

Type II Tree Protection: Layout configuration applies to all parkway strip or public trees near sidewalk.

Type III Tree Protection: Layout for trunk protection applies to all Protected Trees when exclusively authorized for sidewalk cut-out. To be used only with approval from Public Works Operations.

Required protection shall be executed before demolition, excavation or site work occurs.

NOTES:

- CONSTRUCTION PERIOD PROTECTION FOR TREES SHOULD BE PROVIDED BEFORE GRADING OR OTHER EQUIPMENT IS ALLOWED ON THE PROPERTY.
- WHEN CONSTRUCTION IS TO TAKE PLACE BEHIND A TREE CANOPY ON ONE SIDE, THE FENCE SHOULD BE SITED 2 TO 3 FEET BEYOND THAT CONSTRUCTION, BUT BETWEEN CONSTRUCTION AND THE TREE TRUNK.
- IF CONSTRUCTION OR PAVING IS TO TAKE PLACE THROUGHOUT THE AREA BEHIND A CANOPY, AND DRIP LINE FENCING IS NOT PRACTICAL, SNOW FENCING SHOULD BE USED TO PROTECT THE TRUNKS FROM DAMAGE.

1 SNOW FENCING THREE LAYERS OF WIRE AND LATH SNOW FENCING TO 8 FEET ABOVE GROUND ON TREES WHERE CONSTRUCTION WILL TAKE PLACE BEHIND THE CANOPY.

2 TOP OF FENCE WITH FLUORESCENT FLAGGING TAPE HUNG EVERY 10 FEET

3 6' CHAIN LINK OR WELDED WIRE MESH

4 8' FENCE POST OF 2" DIAMETER GI PIPE OR T-ANGLE POST

5 FENCE PLACED AT DRIP LINE OR 50% GREATER THAN THE TREE CANOPY RADIUS WHERE POSSIBLE

ELEVATION

SECTION

PLAN

10/17/2025 PER CITY COMMENTS

9/15/2025 PER CITY COMMENTS

7/25/2025 PER CITY COMMENTS

4/18/2025 PER CITY COMMENTS

3/31/2025 PER CITY COMMENTS

1/8/2025 PER CITY COMMENTS

NO DATE DESCRIPTION

PROJECT NO: 4185.10

CAD DWG FILE: 418510CL - LOT 3.DWG

DESIGNED BY: JN

DRAWN BY: JN

CHECKED BY: ST

DATE: JUNE 6, 2025

SCALE: NONE

(C) HMM

TREE PROTECTION FENCING DETAIL AND NOTES

A **TREE PROTECTION FENCING**

SCALE: NOT TO SCALE

T-4

SURREY FARMS ESTATES
TWIN OAKS DRIVE, LOS GATOS
DEVELOPMENT REVIEW PLAN SET
LOT 3 | APP #S-24-025

PLOTTED: 10/16/2025 12:28 PM

PROJECT TS18510CL PLANNING (418510CL - LOT 3.DWG)

SURREY FARMS ESTATES TWIN OAKS DRIVE, LOS GATOS DEVELOPMENT REVIEW PLAN SET LOT 3 | APP #S-24-025

CONSTRUCTION LEGEND	
SYMBOL	DESCRIPTION
—	6' CLEAR VIEW FENCE
—	RETAINING WALL
—	6' CLEAR VIEW FENCE ON RETAINING WALL
—	6' ALUMINUM PRIVACY FENCE
—	6' ALUMINUM PRIVACY GATE

NOTES:

1. SEE HMH CIVIL PLANS FOR WALL LOCATIONS AND GRADING.
2. PROPOSED FENCE LINES SHALL FOLLOW SITE GRADING, TYPICAL.
3. A MINIMUM VERTICAL CLEARANCE OF 13.5 FEET SHALL BE MAINTAINED OVER FIRE ACCESS ROADS AND DRIVEWAYS.
4. FOR HORIZONTAL AND VERTICAL SPACING FOR PLANTING, SEE SHEET 10.1.
5. CONTRACTOR TO VERIFY ACTUAL CANOPY CLEARANCES WITHIN 100 FT OF EVERY HOME. UNDER ARBORIST SUPERVISION, PRUNE AND TRIM TREES WITHIN ACCORDANCE ON TREE SPACING DIAGRAM ON SHEET 10.1.
6. SEE SHEET 10.5 FOR CONCEPT IMAGERY.



TREE LEGEND	
SYMBOL	BOTANICAL NAME
	ARUBUS UNEDO
	CERCIS OCCIDENTALIS
	FEIJOA SELLOWIANA
	LAGERSTROEMIA INDICA 'NATCHEZ'
	PLATANUS ACERIFOLIA 'COLUMBIA'
	QUERCUS AGRIFOLIA
	QUERCUS DOUGLASII

SHRUB LEGEND	
SYMBOL	BOTANICAL NAME
●	ACHILLEA MILLEFOLIUM 'MOONSHINE'
●	ANIGOZANTHUS FLAVIDUS 'BIG RED'
●	ARCTOSTAPHYLOS 'HOWARD MCMINN'
●	CAREX DIVULSA
●	CEANOHTUS 'CONCHA'
●	CEANOHTUS 'DARK STAR'
●	EPILOBIUM CANUM
●	HETEROMELES ARBUTIFOLIA
●	LEUCADENDRON DISCOLOR
●	MIMULUS AURANTICAS
●	MUHLENBERGIA RIGENS
●	NEPETA X FAASSENII
●	RHAMNUS CALIFORNICA
●	SALVIA SPATHACEA
●	WESTRINGIA FRUTICOSA

GROUNDCOVER LEGEND	
SYMBOL	BOTANICAL NAME
	ARCTOSTAPHYLOS UVA-URSI
	BARK MULCH
	SLOPE STABILIZING - NATIVE HYDROSEED

BIOTREATMENT LEGEND	
SYMBOL	BOTANICAL NAME
	JUNCUS PATENS

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
1/8/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	418510
CAD DWG FILE:	418510CL - LOT 3.DWG
DESIGNED BY:	JN
DRAWN BY:	JN
CHECKED BY:	ST
DATE:	JUNE 6, 2025
SCALE:	1"=20'
© HMH	



10.0

PLANTING PLAN NOTES

CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY TO FURNISH AND INSTALL PLANT MATERIAL AS SHOWN ON THE DRAWINGS AND AS DESCRIBED IN THE SPECIFICATIONS.

UNLESS DESIGNATED ON THE DRAWINGS OTHERWISE, STRUCTURAL IMPROVEMENTS AND Hardscape SHALL BE INSTALLED PRIOR TO PLANTING OPERATIONS.

PLANT LIST ON THE DRAWINGS SHALL BE USED AS A GUIDE ONLY. CONTRACTOR SHALL TAKEOFF AND VERIFY SIZES AND QUANTITIES BY PLAN CHECK.

A SOIL MANAGEMENT REPORT SHALL BE PROVIDED BY LANDSCAPE CONTRACTOR AND SOIL AMENDMENTS SHALL BE FOLLOWED PER THE REPORT. PHYSICAL COPIES OF THE SOIL MANAGEMENT REPORT SHALL BE PROVIDED TO THE CLIENT, PROJECT LANDSCAPE ARCHITECT AND LOCAL AGENCY AS REQUIRED. THE SOIL MANAGEMENT REPORT SHALL CONFORM TO STATE AB1881 WATER EFFICIENT LANDSCAPE ORDINANCE (WELO) OR LOCAL AGENCY ADOPTED WELO. CONTRACTOR SHALL OBTAIN A SOILS MANAGEMENT REPORT AFTER GRADING OPERATIONS AND PRIOR TO PLANT INSTALLATION.

SAMPLES OF FERTILIZERS, ORGANIC AMENDMENT, SOIL CONDITIONERS, AND SEED SHALL BE SUBMITTED PRIOR TO INCORPORATION. CONTRACTOR SHALL FURNISH TO THE OWNER'S AUTHORIZED REPRESENTATIVE A CERTIFICATE OF COMPLIANCE FOR SUCH FURNISHED MATERIALS.

ALL WORK ON THE IRRIGATION SYSTEM, INCLUDING HYDROSTATIC, COVERAGE, AND OPERATIONAL TESTS AND THE BACKFILLING AND COMPACTION OF TRENCHES SHALL BE PERFORMED PRIOR TO PLANTING OPERATIONS.

LOCATIONS OF PLANT MATERIAL SHALL BE REVIEWED ON SITE BY THE OWNER'S AUTHORIZED REPRESENTATIVE PRIOR TO INSTALLATION.

TREES SHALL BE PLANTED NO CLOSER THAN TEN FEET (10') FROM UTILITIES.

TREES PLANTED WITHIN FIVE FEET (5') OF Hardscape OR STRUCTURES SHALL BE INSTALLED WITH A ROOT BARRIER AS APPROVED BY THE OWNER'S AUTHORIZED REPRESENTATIVE.

Defensible Space Zones

Following are guidelines from Santa Clara County Fire Department on how to create and maintain effective defensible space zones:



Zone 1, extends 0 to 5 feet out: The Noncombustible Zone

- Remove all plants and vegetation, especially those touching your home.
- Clean roofs and gutters of dead leaves, debris and pine needles that could catch embers.
- Replace or repair any loose or missing shingles or roof tiles to prevent ember penetration.
- Reduce embers that could pass through vents in the eaves by installing 1/8 inch metal mesh screening.
- Clean debris from exterior attic vents and install 1/8 inch metal mesh screening to block embers.
- Repair or replace damaged or loose window screens and any broken windows.
- Screen or box-in areas below patios and decks with wire mesh to prevent debris and combustible materials from accumulating.
- Move any flammable material away from wall exteriors – mulch, flammable plants, leaves and needles, firewood piles – anything that can burn. Remove anything stored underneath decks or porches.
- Mandated for new construction

Zone 2, extends 30 feet out: The Clean and Green Zone

- Remove all dead plants, grass and weeds (vegetation).
- Remove dead or dry leaves and pine needles from your yard, roof and rain gutters.
- Trim trees regularly to keep branches a minimum of 10 feet from other trees.
- Remove branches that hang over your roof and keep dead branches 10 feet away from your chimney.
- Create a separation between trees, shrubs and items that could catch fire, such as patio furniture, wood piles, swing sets, etc.

ONTRACTOR MUST CONTACT THE CITY OF LOS GATOS ARBORIST TO VERIFY SPECIES (EVEN IF SHOWN ON THE PLANS), LOCATIONS, AND QUANTITIES OF ALL STREET TREES PRIOR TO ORDERING MATERIAL. IF STREET TREES ARE TO BE PLANTED IN TREE WELLS, FINAL LOCATION OF TREE WELLS SHALL BE DETERMINED BY THE ARBORIST PRIOR TO INSTALLATION OF SIDEWALK.

ALL PLANTING AREAS TO RECEIVE 3" THICK BARK MULCH LAYER. CONTRACTOR SHALL PROVIDE SAMPLE OF PROPOSED BARK MULCH FOR APPROVAL. BARK MULCH SHALL BE LYNGSO SMALL FIR BARK (3/4" TO 1-1/2") OR APPROVED EQUAL.

ALL PLANT MATERIAL SHALL BE SELECTED IN ACCORDANCE WITH THE AMERICAN STANDARD FOR NURSERY STOCK (ANSI Z60.1) FOR STANDARD FORM TREES, CALIPER SIZE SHALL BE MEASURED 6" ABOVE THE SOIL LINE FOR CALIPERS EQUAL TO OR LESS THAN 4" FOR CALIPERS GREATER THAN 4", CALIPER SHALL BE MEASURED 12" ABOVE THE SOIL LINE. FOR MULTI-TRUNK TREES THE CALIPER SHALL BE ESTABLISHED BY TAKING THE AVERAGE OF THE CALIPER OF THE TWO LARGEST TRUNKS. CALIPER IS MEASURED 6" ABOVE ORIGIN POINT OF THE SECOND LARGEST TRUNK OR 6" ABOVE GROUND IF ALL TRUNKS ORIGINATE FROM THE SOIL.

CALIPER SIZES STANDARDS:

15 GALLON: 0.75-1.25"

24" BOX: 1.25-2"

36" BOX: 2.3-5"

48" BOX: 3.5-5"

60" BOX: 4-6"

WATER NEEDS CATEGORY BASED ON WUCOLS IV (JANUARY 2014) LANDSCAPE COEFFICIENT METHOD:

CATEGORY PERCENTAGE OF ET₀

(H) HIGH: 0.7-0.9

(M) MEDIUM: 0.4-0.6


(L) LOW: 0.1-0.3

(VL) VERY LOW: <0.1

PROPOSED PLANT PALETTE


SYMBOL	QTY.	BOTANICAL NAME	COMMON NAME	MINIMUM CONTAINER SIZE	HxW	WUCOLS	NOTES	HDS&G RECOMMENDED	OTHER FIRE RESISTANT PLANTS
--------	------	----------------	-------------	------------------------	-----	--------	-------	-------------------	-----------------------------

TREES



1	ARUBITUS UNEDO **	STRAWBERRY TREE	24" BOX	20' X 20'	L	STANDARD FORM	X		
1	CERCIS OCCIDENTALIS *	WESTERN REDBUD	24" BOX	15' X 10'	VL	TREE FORM ONLY		X	
0	FEIJOA SELLOWIANA **	PINEAPPLE GUAVA	24" BOX	20' X 15'	VL	MULTI-TRUNK		X	
0	LAGERSTROEMIA INDICA 'NATCHEZ' **	NATCHEZ CRAPE MYRTLE	24" BOX	25' X 15'	L	MULTI-TRUNK			
0	PLATANUS ACERIFOLIA 'COLUMBIA' **	COLUMBIA LONDON PLANE	36" BOX	60' X 30'	M	STANDARD FORM			
0	QUERCUS AGRIFOLIA *	COAST LIVE OAK	36" BOX	50' X 15'	M	STANDARD FORM	X		
0	QUERCUS DOUGLASII *	BLUE OAK	36" BOX	60' X 30'	VL	STANDARD FORM	X		

SHRUBS



SYMBOL	QTY.	BOTANICAL NAME	COMMON NAME	1 GALLON	3' X 3'	L	X	
--------	------	----------------	-------------	----------	---------	---	---	--

13	ACHILLEA MILLEFOLIUM 'MOONSHINE' *	YELLOW YARROW	1 GALLON	3' X 3'	L			
15	ANIGOZANTHOS FLAVIDUS 'BIG RED' **	BIG RED KANGAROO PAWS	1 GALLON	2' X 2'	L			
1	ARCTOSTAPHYLOS 'HOWARD MCMINN' *	HOWARD MCMINN MANZANITA	1 GALLON	8' X 10'	L	X		
19	CAREX DIVULSA **	FOOTHILL SEDGE	1 GALLON	2' X 2'	L		X	
0	CEANOTHUS 'CONCHA' *	CONCHA CEANOOTHUS	1 GALLON	6' X 8'	L		X	
8	CEANOOTHUS 'DARK STAR' *	DARK STAR CEANOOTHUS	1 GALLON	5' X 6'	L		X	
30	EPILOBIUM CANUM *	CALIFORNIA FUCHSIA	1 GALLON	3' X 3'	L		X	
1	HETEROMELES ARBUTIFOLIA *	TOYON	1 GALLON	8' X 5'	L		X	
12	LEUCADENDRON DISCOLOR **	CONEBUSH	5 GALLON	6' X 6'	L			
12	MIMULUS AURANTICAS *	STICKY MONKEY FLOWER	1 GALLON	4' X 4'	L		X	
58	MUHLENBERGIA RIGENS *	DEER GRASS	1 GALLON	4' X 4'	L		X	
25	NEPETA X FAASSENII **	CATMINT	1 GALLON	1' X 2'	L			
3	RHAMNUS CALIFORNICA *	CALIFORNIA COFFEEBERRY	1 GALLON	8' X 8'	L		X	
0	SALVIA SPATHACEA *	HUMMINGBIRD SAGE	1 GALLON	5' X 4'	L	UPRIGHT FORM	X	
20	WESTRINGIA FRUTICOSA **	COAST ROSEMARY	1 GALLON	4' X 4'	L			

SYMBOL	QTY.	BOTANICAL NAME	COMMON NAME	SPREAD	SPACING	
--------	------	----------------	-------------	--------	---------	--

ARCTOSTAPHYLOS UVA-URSI *	BEARBERRY	1 GALLON	1' X 4'	SET @ 36" O.C.	X	
---------------------------	-----------	----------	---------	----------------	---	--

BARK MULCH	BARK MULCH					
------------	------------	--	--	--	--	--

SLOPE STABILIZING - NATIVE HYDROSEED HYDROSEED						
--	--	--	--	--	--	--

SYMBOL	QTY.	BOTANICAL NAME	COMMON NAME	SPREAD	
--------	------	----------------	-------------	--------	--

34	JUNCUS PATENS	CALIFORNIA GRAY RUSH	1 GALLON	2' X 2'	
----	---------------	----------------------	----------	---------	--

NOTES:

- *NATIVE PLANT
- **ADAPTIVE PLANT
- BARK MULCH: ALL PLANTING AREAS TO RECEIVE A 3" THICK LAYER OF BARK MULCH.
- BIOTREATMENT PLANTING AREAS TO RECEIVE A 3" THICK LAYER OF NON-FLOATABLE BARK MULCH.
- TREE SPECIES TO BE APPROVED BY TOWN ARBORIST.


10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
1/8/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	418510
CAD DWG FILE:	418510CL - LOT 3.DWG
DESIGNED BY:	HMH
DRAWN BY:	JN
CHECK	

SURREY FARMS ESTATES
TWIN OAKS DRIVE, LOS GATOS
DEVELOPMENT REVIEW PLAN SET
LOT 3 | APP #S-24-025

DEVELOPMENT REVIEW PLAN SET
LOT 3 | APP #S-24-025


1

PROJECTS\418510\ANNING\418510C1 - 1013.DWG




H 6' CLEAR VIEW FENCE ON RETAINING WALL


SCALE: 1/2" = 1'-0"




E TREE PLANTING ON SLOPE




C GROUNDCOVER
SCALE: 1" = 1'-0"




A TREE



B SHRUB
SCALE: 1" = 1'-0"



A TREE



LANDSCAPE DETAILS

SURREY FARMS ESTATES

TWIN OAKS DRIVE, LOS GATOS

DEVELOPMENT REVIEW PLAN SET

LOT 3 | APP #S-24-025

<p>I DRIPLINE INSTALLED ON GRADE</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. SEE IRRIGATION LEGEND SPECIFICATION 2. INSTALL ALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS</p>	<p>F ON GRADE TREE BUBBLER</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. BUBBLER DISTANCE TO ROOT BALL WILL VARY DEPENDING ON THE CONTAINER SIZE OF THE PLANT. ALLOW 6" BETWEEN TRUNK AND BUBBLER. 2. PLACE ALL BUBBLERS ON UPHILL SIDE OF SLOPE IF APPLICABLE. CONCEAL ALL EQUIPMENT UNDER MULCH. 3. SEE IRRIGATION LEGEND FOR SPECIFICATION. 4. INSTALL ALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.</p>	<p>C ANTI-SIPHON PLASTIC CONTROL VALVE</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. SET VALVE 12" MIN. ABOVE HIGHEST SPRINKLER SERVED OR PER CODE. 2. SEE PLANS, LEGEND AND SPECIFICATIONS FOR ADDITIONAL INSTALLATION NOTES.</p>
<p>H DRIPLINE OPERATION INDICATOR</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. USE ONE OPERATION INDICATOR PER ZONE. 2. PLACE AT FLUSH END OF ZONE. 3. SEE IRRIGATION LEGEND FOR PIPE SCHEDULE AND EQUIPMENT SPECIFICATION. 4. INSTALL ALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.</p>	<p>E QUICK COUPLING VALVE</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. NIPPLES AND FITTINGS TO BE SAME SIZE AS VALVE IPT INLET THREAD SIZE 2. SEE IRRIGATION LEGEND FOR SPECIFICATION 3. INSTALL ALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS</p>	<p>B BALL VALVE</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. PLACE AGGREGATE PRIOR TO INSTALLATION OF VALVE BOX 2. INSTALL VALVE BOX SO TOP OF BOX IS FLUSH WITH ADJACENT HARDSCAPE</p>
<p>J DRIPLINE CENTER - FEED LAYOUT</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. SEE IRRIGATION LEGEND FOR EQUIPMENT SPECIFICATION 2. INSTALL ALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS 3. THE TOTAL LENGTH OF ALL INTERCONNECTED DRIP LINE SHALL NOT EXCEED THE MAXIMUM RUN LENGTH</p>	<p>G DRIPLINE FLUSH VALVE</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. SEE IRRIGATION LEGEND FOR EQUIPMENT SPECIFICATION 2. INSTALL ALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS 3. LOCATE AND USE ONE FLUSH VALVE FOR EVERY 7 GPM PER ZONE AT LOW POINTS.</p>	<p>D DRIP ANTI-SIPHON PLASTIC CONTROL VALVE</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. SET VALVE 12" MIN. ABOVE HIGHEST SPRINKLER SERVED OR PER CODE 2. SEE PLANS, LEGEND AND SPECIFICATIONS FOR ADDITIONAL INSTALLATION NOTES</p>
<p>A WALL MOUNT CONTROLLER</p> <p>SCALE: N.T.S.</p> <p>NOTES: 1. VERIFY LOCATION WITH PROJECT ELECTRICIAN 2. ALL ELECTRICAL WORK MUST CONFORM TO LOCAL CODES. REFER TO PRODUCT LITERATURE FOR ADDITIONAL INSTALLATION REQUIREMENTS. THIS DRAWING IS PROVIDED FOR REFERENCE ONLY. INDIVIDUAL PROJECT REQUIREMENTS AND LOCAL CODES MAY DICTATE DIFFERENCES IN INSTALLATION PROCEDURES THAT ARE NOT IDENTIFIED ON THIS DETAIL.</p>	<p>C IRRIGATION DETAILS</p> <p>10/17/2025 PER CITY COMMENTS 9/15/2025 PER CITY COMMENTS 7/25/2025 PER CITY COMMENTS 4/18/2025 PER CITY COMMENTS 3/31/2025 PER CITY COMMENTS 1/8/2025 PER CITY COMMENTS NO DATE DESCRIPTION PROJECT NO: 418510CL-10 CAD DWG FILE: 418510CL-10.DWG DESIGNED BY: HMH DRAWN BY: HMH CHECKED BY: ST DATE: JUNE 6, 2025 SCALE: NONE © HMH</p>	<p>10.4</p>

**SURREY FARMS ESTATES
TWIN OAKS DRIVE, LOS GATOS
DEVELOPMENT REVIEW PLAN SET
LOT 3 | APP #S-24-025**

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
1/8/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	4185.10
CAD DWG FILE:	418510CL - LOT 3.DWG
DESIGNED BY:	HMH
DRAWN BY:	HMH
CHECKED BY:	ST
DATE:	JUNE 6, 2025
SCALE:	NONE
(C) HMH	

CONCEPT IMAGERY



10.5



E 6' CLEAR VIEW FENCE
COLOR SHALL BE BLACK



D 6' ALUMINUM PRIVACY FENCE AND GATE
COLOR SHALL BE BLACK



C RETAINING WALL
SHALL BE VARIEGATED CMU WITH WALL CAP FROM ORCO BLOCK AND Hardscape
COLOR SHALL BE BORREGO
SPLIT FACE ON EXPOSED SURFACE
LRV SHALL BE MAX 30%



FRONT PORCH WALL MOUNT LIGHT



OUTDOOR WALL MOUNT LIGHT



POST LIGHT

P SITE LIGHTING
SCALE: NONE

LIGHTING LEGEND	
SYMBOL	DESCRIPTION
◆	FRONT PORCH WALL MOUNT LIGHT
◆	OUTDOOR WALL MOUNT LIGHT
◆■	POST LIGHT

SITE LIGHTING REQUIREMENTS:


ORIENT ALL SITE LIGHTING DIRECTLY DOWNWARDS TO PREVENT LIGHT POLLUTION AND EXCESS FLARE IN THE PUBLIC REALM.

ILLUMINATE A ZONE OF A MAXIMUM OF FIVE FEET IN FRONT OF THE GROUND FLOOR FAÇADE FOR ALL ACTIVE FRONTAGES.

KEEP THE MAXIMUM COLOR TEMPERATURE FOR OUTDOOR LIGHTING BELOW 2700 KELVIN, EXCEPT FOR OUTDOOR DECORATIVE LIGHTING FROM NOVEMBER 15 TO JANUARY 15.

SITE LIGHTING NOTES:

1. THE USE OF ENERGY EFFICIENT LIGHTING IS STRONGLY ENCOURAGED.
2. ALL PERMANENT EXTERIOR LIGHT FIXTURES SHALL UTILIZE SHIELDS SO THAT NO BULB IS VISIBLE AND TO ENSURE THAT LIGHT IS DIRECTED TO THE GROUND SURFACE AND DOES NOT SPILL LIGHT ONTO NEIGHBORING PARCELS OR PRODUCE GLARE WHEN SEEN FROM NEARBY HOMES. DECORATIVE LIGHTING FIXTURES ARE PREFERRED FOR SECURITY LIGHTING FIXTURES.



LEO

Specification Sheet | LE300

landscapeforms

Lens Height and Pole Configuration Selection Guide

Poles are manufactured from seamless aluminum alloy with a flush mounted hand hole cover. Poles are pre-drilled to suit the specified mounting conditions prior to powdercoating, and include flush top pole cap, configured to support installation of ANSI C136.41 twist-lock receptacle when specified. Pole base plate is cast aluminum and includes either a two-piece cast aluminum decorative base cover, or four cast aluminum nut covers. Mounting template and anchor hardware included. Anchor bolts conform to ASTM F1154 Grade 55 and are provided with two hex nuts and two flat washers. Bolts have an "L" bend on one end and are galvanized a minimum of 12" on the threaded end.






LE-20-A

20ft / 6m

300 Series - 50 LED LO CLR lens at 20'

Performance light engine @ 3000K

1.0fc 0.5fc 0.2fc



**SURREY FARMS ESTATES
TWIN OAKS DRIVE, LOS GATOS
DEVELOPMENT REVIEW PLAN SET
LOT 3 | APP #S-24-025**

10/17/2025	PER CITY COMMENTS
9/15/2025	PER CITY COMMENTS
7/25/2025	PER CITY COMMENTS
4/18/2025	PER CITY COMMENTS
3/31/2025	PER CITY COMMENTS
1/8/2025	PER CITY COMMENTS
NO DATE	DESCRIPTION
PROJECT NO:	418510CL
CAD DWG FILE:	418510CL - LOT 3.DWG
DESIGNED BY:	JN
DRAWN BY:	JN
CHECKED BY:	ST
DATE:	JUNE 6, 2025
SCALE:	1"=20'
(C) HMH	

**CONCEPTUAL
LIGHTING PLAN**